

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 24 N.R. 8 W


Missaukee COUNTY

DESCRIPTION OF CORNER 1/4 corner common to sections 11-12

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 5-25-67

WITNESSES TO CORNER.....



18" W. Pine Stp S 25 W 61.0'

16" R. Pine Stp N 72 W 38.0'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by proportionate measurement, midpoint on line between section corners. No original evidence.

SURVEYOR'S SEAL

SIGNED Kenneth Ostling DATE 6-15-67
REGISTERED LAND SURVEYOR #10068