

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Missaukee County</u> <small>(County)</small>	Located In:	Corner Code <u>≠</u>
1. Public Land Survey	T <u>24N</u> R <u>8W</u>	<u>E-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7					⊕								
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Carl F. Roser, in a field survey on February 6, 19 86, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-7 - Restored NE Cor. of Sec. 20 from two Co. Surveyor J.G.Cavanagh 1909 N.B.T.'s; White Pine 18" (now a stump), N47°W, 31.0' and White Pine 36" (now a stump), S26°W, 35.0'; where post bottom remains was also recovered that fit the N.B.T.'s. Cor. fits U.S. (G.L.O.) resurvey tie North 2418' to north edge of Hopkins Creek & fits G.L.O. & J.G.C. tie ½ mile south (reasonable) to E½ Cor. of Sec. 20. A ½" pipe, 6" above ground (painted white) is N09°45'W, 98.4'; this pipe is believed to have been set by local land owner at temp. 80 chain marker from North on Random line (Conservation Dept. 1966 Random line).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7

Set DNR monument & cedar post		
10" Maple	N65°W	34.0'
5" Maple (clp)	N35°E	37.9'
3" Red Oak	S85°E	29.0'
12" Maple (clp)	S75°W	34.1'
Ctr winding E-W trail	Due N	389'



Signed by Carl F. Roser 7-23-86 Date _____
 Surveyor's Michigan License No. #12028