

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Missaukee County  
(County)

Located in: \_\_\_\_\_ Corner Code E-9

- |                                    |                                      |            |
|------------------------------------|--------------------------------------|------------|
| 1. Public Land Survey              | T <u>24N</u> R <u>8W</u>             | <u>E-9</u> |
|                                    | T _____ R _____                      | _____      |
|                                    | T _____ R _____                      | _____      |
|                                    | T _____ R _____                      | _____      |
| 2. Property Controlling in Section | S <u>20</u> T <u>24N</u> R <u>8W</u> | <u>7</u>   |
|                                    | S _____ T _____ R _____              | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____              | _____      |
|                                    | S _____ T _____ R _____              | _____      |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Carl F. Roser, in a field survey on February 7, 19 86, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

7 - Restored SE corner of NE $\frac{1}{4}$  of NE $\frac{1}{4}$  of Sec. 20 mid-way & on line between fd. NE cor. & E $\frac{1}{4}$  Cor. of Sec. 20 per J.G. Cavanagh Sur. & Sec. Sub'n. of Sec. 21 in 1909. A R.R. Ir. as called for in JGC notes has been removed by others & may have been moved to another position prior to being removed. Fences in this area are "screwy". 1/8 Cor. as set this survey fits Co. Surveyor JGC wits close (JGC had White Pine 6", SE, 8' - we fd. pine stub, S50°E, 5.6').


E-9 - Fd. Dept. mon. at old cor. fn. post (mostly down) & large steel fn. post (fn. remains N-S-E-W). Previous Dept. (DNR) Cor. of Record (KJO-1967) that fits 1909 J.G. Cavanagh Sur. of Section 21 & J. Wilcox survey. U.S. B.T. stump S.E. (with partial face) in place; also noted by J.G. Cavanagh in 1909.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

7  
 Drove 5/8" x 34" rerod w/RLS Cap & set cedar post w/loc tag  
 3" Oak N64°E 7.8'  
 5" Maple(clp) S82°W 23.2'  
 8" Red Pine N36°W 28.1'  
 6" Maple(clp) N08°E 27.5'  
 Fd 1" angle Ir. at newer fn post N22°W 104.9'

E-9  
 Fd. Dept. Mon. & Large steel fn. post and set cedar post  
 15" Aspen N16°E 4.96'  
 11" White Pine S55°W 43.99'  
 4" Maple N46°W 17.32'  
 7" Aspen S08°W 29.33'

Signed by Carl F. Roser 7-23-86 Date \_\_\_\_\_  
 Surveyor's Michigan License No. #12028



BOARD OF LAND SURVEYORS, JAN. 29, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983