

**SURVEY & REMONUMENTATION**

MAY 28 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

LIBER 308 PAGE 700

#1069

For corners in <u>Missaukee</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>24N</u> R <u>8W</u>	<u>C-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MISSAUKEE COUNTY MICHIGAN

RECORDED **DEC 20 1996** *JHS AM*

*Carolyn Flare*  
REGISTER

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		6		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, J. Dean Geers, in a field survey on December, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- C-13) 1838 GLO section post by John Brink, Deputy Surveyor; Sugar 10-N53E-13, Sugar 24-N37W-39
- C-13) 1900 Co. Survey in Section 5, T23N, R8W; Corner was used, no wit's recorded
- C-13) 1915 Beuthien Survey in Section 31, T24N, R8W; Iron post and stone; Poplar 10-N29W-89, WPS 17-S48W-78
- C-13) 1979 Wilcox Survey, Liber S-1, Page 478; Found 1/2" rerod
- C-13) 1979 Wilcox LCRC, Liber 1, Page 552; Found 1/2" rerod, S50E-52.40-T. Riser, S20E-85.65-P.P., N40E-53.11-3" Cedar, N40W-75.18-6" Cottonwood

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- C-13) Section Corner common to Sections 31 and 32, T24N, R8W and Sections 6 and 5, T23N, R8W; Found iron of record. Corner is 1± Southerly centerline East and West Road and in centerline road to South, 5± Easterly centerline road to North. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- C-13) Set Miss. Co. Mon. on 1/2" Iron in mon. box.  
 N30E - 53.09' - 6" Cedar  
 S50E - 52.40' - Top center tel. pedestal  
 S20E - 85.62' - P.P.  
 N50W - 63.20' - Set Iron

Peer Group Reviewed and Approved  
 Date: 12-19-96  
*J. Dean Geers*  
 J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers* Date 12-19-96  
 Surveyor's Michigan License No. 33977

