

SURVEY & REMONUMENTATION

MAY 28 1997

LIBER 308 PAGE 701

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1070

For corners in Missaukee (County) Located In: _____ Corner Code # _____

| | | | | | | |
|--------------------------------------|---|------------|---|-----------|-------------|-------|
| 1. Public Land Survey | T | <u>24N</u> | R | <u>8W</u> | <u>D-13</u> | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| 2. Property Controlling in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |

MISSAUKEE COUNTY MICHIGAN

RECORDED **DEC 20 1996** *J.D.G.*

Rosalyn Flare
 REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, J. Dean Geers, in a field survey on December, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- D-13) 1838 GLO quarter section post by John Brink, Deputy Surveyor; Beech 10-N43E-43, Hemlock 13-N47W-18
- D-13) 1900 Co. Survey in Section 5, T23N, R8W; Cedar stake 28" long, 3x3 with bottles and broken crockery around it.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- D-13) Corner common to Section 32, T24N, R8W and Section 5, T23N, R8W. Found pk. nail 1.5' North of East-West Road centerline and on fence line to the North. This position fits close to a prorated location between the section corners one half mile East and West compared to the 1900 Co. Survey. This corner is accepted as the best available evidence of the position of the original corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-13) Set 1/2" Iron with Missaukee Co. Mon. in iron box

North - 36.62 - Fence Post, Fd. nail
 S45E - 72.33 - 12" R. Pine, Fd. nail
 S05E - 56.85 - 16" R. Pine, Fd. nail
 N 72W - 86.22 - 8" W. Pine, Fd. nail

Peer Group Reviewed and Approved

Date: 12-19-96
J. Dean Geers
 J. Dean Geers, Missaukee Co. Representative

Signed by _____

Date 12-19-96

Surveyor's Michigan License No. 33577

