

SURVEY & REMONUMENTATION

JAN 16 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

#1180

LIBER 314 PAGE 1261

For corners in

| | | |
|------------------------------------|--------------|---------------|
| <u>Missaukee</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T24NR 8W | H-13 |
| | T___R___ | _____ |
| | T___R___ | _____ |
| | T___R___ | _____ |
| 2. Property Controlling in Section | S___T___R___ | _____ |
| | S___T___R___ | _____ |
| 3. Miscellaneous Property in Sec. | S___T___R___ | _____ |
| | S___T___R___ | _____ |

MISSAUKEE COUNTY MICHIGAN
RECORDED NOV 10 1997 4:30 pm

Reslynn Glass
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

I, J. Dean Geers, in a field survey on June, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- H-13) 1838 GLO Quarter Section Post by John Brink, Deputy Surveyor; Hemlock 10-N27E-28, Beech 8-N66W-31
- H-13) County Surveyor Notes; Corner Witnesses, Elm 16-S28E-89, Elm 8-N22E-218
- H-13) 1982 Lake State Survey & Engineering Survey, Liber S-2, Page 85 in Section 3, T23N, R8W; Found Railroad Spike in intersection of roads; South 34.65 - 3" White Pine, N53E-76.68-8" Scotch Pine, N22W- 43.38-10" Cottonwood
- H-13) 1995 Wade-Trim Survey, Liber S-3, Page 256 in Section 3, T23N, R8W; Reset corner per survey recorded in Liber S-2, Page 85; N50E-76.35 - 10" Red Pine, N20W-43.28-14" Cottonwood, S30E-33.50-6" Ash, S30W-37.12-5" Ash.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- H-13) Quarter Corner common to Section 34, T24N, R8W and Section 3, T23N, R8W; Found Iron and Cap of record ±5' North of East-West road centerline and ± 6' Westerly of centerline road to North. This corner is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-13) Set Missaukee County Monument on 1/2" Iron
S23E 33.44 8" Elm, Found Nail
S52W 37.11 6" Elm, Found Nail
N20W 43.38 20" Cottonwood, Found Nail
N78E 88.75 10" Elm

Peer Group Reviewed and Approved

Date: 10-15-97
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by _____
Surveyor's Michigan License No. 33977 No. _____



Date 10-22-97