

SURVEY & REMONUMENTATION

JAN 16 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Missaukee

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--|-------------|
| 1. Public Land Survey | T <u>24</u> N <u>R</u> 8W | <u>J-13</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

#1182

LIBER 314 PAGE 1263

MISSAUKEE COUNTY MICHIGAN

RECORDED NOV 10 1997 4 30 pm

Paulyn Flor
REGIS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, J. Dean Geers, in a field survey on June, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- J-13) 1838 GLO Quarter Section Post by John Brink, Deputy Surveyor; Birch 14-N79E-21, Beech 10-N73W-47
- J-13) 1888 County Survey notes of survey in Section 35, T24N, R8W; Elm 7-N79W-89, Corner Fence Post-NE-42.2
- J-13) 1977 Wilcox LCRC, Liber 1, Page 203; Found 3/8" Iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- J-13) Quarter Corner common to Section 35, T24N, R8W and Section 2, T23N, R8W; Found 1/2" Iron in Pipe ±3' deep. Corner is ±2' North of centerline East-West road and ±20' Easterly of fence line to North. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


- J-13) Found Pipe and raised with 1/2" Iron and Missaukee County Monument
 - N65W 71.95 14" Twin Ash
 - N70E 64.86 14" Elm
 - S65E 94.30 Set Iron
 - S65E 110.47 Set Iron

Peer Group Reviewed and Approved

Date: 10-22-97
J. Dean Geers

J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers*
Surveyor's Michigan License No. 33977



Date 10-22-97