

SURVEY & REMONUMENTATION

JAN 16 1998

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

#1183

SECTION

For corners in

Missaukee

(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|---------------|--------------|------|
| 1. Public Land Survey | T <u>24</u> N | R <u>8</u> W | K-13 |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

LIBER 314 PAGE 1264

MISSAUKEE COUNTY MICHIGAN
RECORDED NOV 10 1997 4:30 PM

Pauline Flores
REC
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, J. Dean Geers, in a field survey on June, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		5		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- K-13) 1838 GLO Section Post by John Brink, Deputy Surveyor; Beech 10-N18E-29, Beech 9-N8½W-26
- K-13) 1853 GLO Subdivision by Whelpley; Beech 8-N9¼W-29, Hemlock 10-N70¼E-25
- K-13) 1977 Wilcox LCRC, Liber 1, Page 203; Found 1" Pipe; N48E-52.02-3" Maple, N35W-54.98-3" Maple, S76W-92.09-2" Cedar

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-13) Section Corner common to Sections 35 and 36, T24N, R8W and Sections 1 and 2, T23N, R8W; Re-established Corner from Found 1/8th Iron and Quarter Corner to the East of this Corner. This corner is accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


- K-13) Set ½" x 18" Rerod with Missaukee County Monument
 - N45E 87.70 10" Maple
 - N25E 60.09 4" Red Pine
 - N20W 67.74 12" White Pine
 - S25W 59.24 Power Pole

Peer Group Reviewed and Approved

Date: 10/15/97

J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by _____
Surveyor's Michigan License No. 33987



Date 10-20-97