

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: \_\_\_\_\_ Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
Missaukee (County)

- |                                      |   |            |   |           |       |       |
|--------------------------------------|---|------------|---|-----------|-------|-------|
| 1. Public Land Survey                | T | <u>24N</u> | R | <u>8W</u> | K1    |       |
|                                      | T | _____      | R | _____     | _____ |       |
| 2. Property Controlling in Section   | S | _____      | T | _____     | R     | _____ |
|                                      | S | _____      | T | _____     | R     | _____ |
| 3. Miscellaneous Property in Section | S | _____      | T | _____     | R     | _____ |
|                                      | S | _____      | T | _____     | R     | _____ |

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on Oct. 30, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1											●		
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

- |  |   |
|--|---|
| <p><u>K1</u> - GLO - Forked W. Pine 18" dia. Cor. Sec. 35 &amp; 36<br/>                 T25N, R8W - J. Brink - 1838<br/>                 - GLO sub - T24N, R8W - T. Whelpley - 1853<br/>                 W. Pine 20" for corner<br/>                 Maple 6" S24½°E 24 L.<br/>                 Nor. Pine 12" S51½°W 56 L.<br/>                 - Fargo Eng. - 1912 - Fd. tree noted as corner lying down w/ scribe marks plain. Set iron post and broken crockery. W. Pine Stp. 18" N58½°W 0.85 Ch.</p> | <p>- DNR Cor. Rec. - K. J. Ostling - 1967<br/>                 Fd. Fargo mon. Fd. Fargo NBT Stp.<br/>                 Set 1" pipe w/ 4" Alum. Cap<br/>                 6" R. Pine West 4.2'<br/>                 7" R. Pine N26°W 75.2'</p> |
|--|---|

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

K1 - Standard Sec. Corner common to Sec. 35 & 36, T25N, R8W and Sec. 1 & 2, T24N, R8W - Fd. 4" DOC (DNR) Alum. Cap on 1" iron pipe per Ostling. Fd. scribed cedar post on SW side and Fd. 2" Iron guard pipe on NE side. Also fd. remains of Fargo's WPS in agreement w/ Mon. DOC (DNR) Mon. accepted as a careful and faithful perpetuation of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K1 - 4" DOC (DNR) Alum. Cap on 1" Galv. iron pipe  
 WNW 0.5' to Fd. Blue Carsonite Post  
 S86°W 4.58' to set N & T in S. side 16" R. Pine (KJO)  
 N28°W 75.30' to set N & T in NE side Tw. 19" R. Pine (KJO)  
 N60°W 49.12' to set N & T in NE side 18" R. Pine  
 S1°W 68.88' to set N & T in E side Tw. 20" R. Maple  
 S80°E 20.92' to set N & T in S side 8" R. Pine scribed 'XBT'



Signed by: Craig W. McVean  
 Surveyor's Michigan License No.: 39088

Date: 5/20/2004