

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Missaukee Located In _____ Corner Code # _____
(County)

1. Public Land Survey		T	<u>24N</u>	R	<u>8W</u>	<u>L4</u>
		T	<u>24N</u>	R	<u>8W</u>	<u>L6</u>
2. Property Controlling in Section	S	T	_____	R	_____	_____
	S	T	_____	R	_____	_____
3. Miscellaneous Property in Section	S	T	_____	R	_____	_____
	S	T	_____	R	_____	_____

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on April 15, 2004 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

L4 – CSR – E.A. Beuthien – 1914 L6 – None
 Stake and stone
 Hemlock 13" N62½°E 29 L.
 Maple 36" N33°W 40 L.



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

L4 – Center ¼ Cor. Sec. 12 – No conclusive evidence of Beuthien position found. Set 2" Alum. Cap on 5/8" x 34" iron rebar at intersection of ¼ lines. Found old down E-W barb wire fence is 4'± S. L6 – C ¼, Sec. 13 – Set 2" Alum. Cap on 5/8" x 34" iron rebar at intersection of ¼ lines.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p><u>L4</u> – Stamped 2" Alum. Cap on 5/8" x 34" rebar N34°W 23.78' to set N & T in NW side 10" R. Maple N20°E 30.63' to set N & T in NW side 5" R. Maple N75°E 30.33' to set N & T in N side Tw. 29" Oak S28°E 2.98' to set N & T in E side 8" R. Maple Set blue carsonite post w/ loc. tag 0.8' N.</p>	<p><u>L6</u> – Stamped 2" Alum. Cap on 5/8" x 34" rebar N65°W 10.79' to set N & T in NE side 15" R. Maple N35°E 18.43' to set N & T in E. side 9" Cedar S58°W 45.55' to set N & T in N. side 18" R. Maple S10°W 30.42' to set N & T in E. side 16" Cedar Set blue carsonite post w/ loc. tag 1' NNE</p>
--	--

Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 5/20/2004