

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Missaukee Located In _____ Corner Code # _____
(County)

- | | | | | | |
|--------------------------------------|---|-------|---|-------|-------|
| 1. Public Land Survey | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | 12 | T | 24N | R 8W |
| | S | 12 | T | 24N | R 8W |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Apr. 5, 2004 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 9 - CSR - E.A. Beuthien - 1914 Cedar Post - Maple 24" S84°W 50 11 - None

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 9 - CE 1/16; Sec. 12 - No evidence of Beuthien Cor. - Set 2" Alum cap on 5/8" x 34" iron rebar per standard BLM procedure. E-W down fence remains are 3'± N.
11 - SW 1/16, Sec. 12 - Set 2" Alum. Cap on 5/8" x 34" iron rebar per standard BLM procedure. Centerline of N-S 2-track is 4'± E. Remains of N-S fence is 9'± E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 9 - Stamped 2" Alum. Cap on 5/8" x 34" rebar
 N16°W 11.21' to set N & T in W. side 9" Oak
 N78°E 25.14' to set N & T in N. side 6" Oak
 S28°E 18.39' to set N & T in E side 10" Oak
 N79°W 31.69' to set N & T in SW side 6" Ironwood
 Set blue carsonite post with loc. tag 0.9' NE
11 - Stamped 2" Alum. Cap on 5/8" x 34" rebar
 N65°W 7.02' to set N & T in S. side 8" S. Pine
 N15°E 63.37' to set N & T in E. side 8" Cherry
 N77°E 50.16' to set N & T in NW side 10" S. Pine
 S10°E 48.34' to set N & T in E. side 10" Cherry
 Set blue carsonite post 1' NW

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Signed by:

Craig W. McVean

Date:

5/20/2004

Surveyor's Michigan License No.:

39088