

Montmorency County Remonumentation

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Montmorency</u> (County)	Located In:	Corner Code #:
1. Public Land Survey	T <u>29N</u> R <u>1E</u>	<u>A-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED
 MONTMORENCY COUNTY
 DEEDS
 REGISTER
 DEC 28 9 04 AM '93
 A. PANGAM-MCELROY
A. Pangam-McElroy

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1	6	5	4	3	2	1						
2												
3	7	8	9	10	11	12						
4												
5	18	17	16	15	14	13						
6												
7	19	20	21	22	23	24						
8												
9	30	29	28	27	26	25						
10												
11	31	32	33	34	35	36						
12												
13												

I, Larry G. Beauregard in a field survey on May, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-2) GLO post by John Hodgson May 1839.
 Wits: Pine 18" S 63° W 21 links
 Pine 14" N 62° W 21 links

G.F. De La Mater Otsego Co. Surveyor in 1933 P.S. #693. Stanley O. Thorson P.S. #5788 in 1950
 Fnd. both Gov't B's. Placed 1/2" x 30" Fnd. 1/2" bar when making the Plat of
 bar in Cor. Wits: (Y. Pine stp. 20" S 84° E J.R. Trevas-Silver Beach No. 1.
 26.6') (Y. Pine stp. 20" N 61° E 41.5') No wits marked.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-2) Fnd. 3/4" bar C/L Meridian line Road (No I.D. cap).
 Set Mon: Box & placed 3" dia. Aluminum cap marked Montmorency Co. Re-mon. Cor. on same.

Note: THE POSITION OF THIS CORNER AGREES VERY WELL WITH REC. DISTANCE BY DE LA MATER IN 1933 N. & S. IT IS NOT KNOWN WHO RE-SET THIS CORNER AFTER THE REBUILDING OF MERIDIAN LINE ROAD.



C. Description of monument for corner and accessories established to perpetuate locating the position:

(A-2) 1/4 Cor. Comm. to Sec's 1, T29N, R1E & Sec. 6, T29N, R1W
 3/4" bar & Re-Mon. cap P.S. #18654 in Mon. box. Accepted as a perpetuation of the original government corner, approved by the Peer Group on September 24, 1993.
 Wits: S 50° W 67.36' 11" R. Oak N 60° W 64.66' 13" R. Oak
 S 55° E 130.08' 27" R. Oak S 20° W 141.64' P. Pole
 (Placed 20 penny spike & P.S. #18654 in each) (typ)

Signed by Larry G. Beauregard Date 12-27-93
 Surveyor's Michigan License No. 18654