

Montmorency County Remonumentation

Libs 12 Page 43

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Montmorency</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>29N</u> R <u>1E</u>	<u>A-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED
 MONTMORENCY CITY
 REGISTER OF DEEDS
 DEC 28 9 04 AM '93
 A. PANIGAN-MCELROY

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Larry G. Beauregard, in a field survey on May, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-6) GLO Post set by John Hodgson May 1839.
 Wits: (Pine 24" N 47° W 19 links) (Pine 22" S 14° W 29 links)
 G.F. De La Mater P.S. # 693 (Otsego Co. Surveyor) in 1933 fnd. both B.T.'s & Post & set 1/2" x 30" bar. Wits marked: (W. Pine stp. N 84° E 88.1') (W. Oak 4" S 54° E 68.1') (W. Oak 6" S 51° W 137.0').
 Stanley O. Thorson P.S. #5788 in 1956 fnd. bar & wits above.
 Donald E. Marlatt P.S. #18660 in 1981 fnd. bar. Wits marked: (S 85° E 20" Pine 39.9') (N 75° E 9" Maple 51.05') (N 50° W 8" Poplar 51.6').
 Donald E. Sagasser P.S. #14770 (Otsego Co. Rd. Comm. Surveyor) in 1983 fnd. 1/2" bar & wits by Marlatt, then marked one more: (7" Oak S 52° E 68.33') (Meridian Line Rd. Survey).
 Sagasser also re-set 1/2" pipe & Mon. box in 1984, after the construction & paving of said Road.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-6) Fnd. 1/2" pipe in Mon. box on the C/L of Meridian Line Rd. (No I.D. cap).
 (Placed 3" dia. Aluminum cap marked Montmorency Co. Re-Mon. Cor. on same.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-6) 1/4 Cor. Comm. to Sec. 18, T29N, R1E, & Sec. 13, T29N, R1W
 1/2" pipe & Re-Mon. cap #18654 in Mon. box. Accepted as a perpetuation of the original government corner, approved by the Peer Group on September 24, 1993.
 N 25° E 114.23' P. Pole (New) S 75° E 90.5' 15" Norway
 S 75° W 89.68' 8" Norway N 55° W 73.8' 5" Norway
 (Placed blaze, 20 penny spike & P.S. tag #18654) (typ)

Signed by Larry G. Beauregard
 Surveyor's Michigan License No. 18654

Date 12-27-93

FORM APPROVED BY MICHIGAN STATE BOARD

