

### Montmorency County Remonumentation

#### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

08345

For corners in

<u>Montmorency</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>29N</u> R <u>1E</u>	<u>A-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED  
MONTMORENCY CITY  
RECORDS  
DEC 28 9 05 AM '93  
A. FANGLAN-NEELROY  
Register of Deeds Stamp & File Number

I, Larry G. Beauregard in a field survey on May, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(A-12) GLO Post set by John Hodgson May 1839.  
Wits: Pine 8" S 35° W 24 links Pine 6" N 42° W 13 links  
G.F. De La Mater P.S. # 693 (Otsego Co. Surveyor) in 1933 set 1/2" x 30" bar  
Wits: (W. Oak 6" N 49 1/2° W 68.6') (W. Oak 6" S 50° W 27.7') (B. Oak 6" N 27° W 24.0')  
(Spruce Pine 12" S 20° E 6.4')  
George D. Henning P.S. #2240 in 1947 fnd. 1/2" bar & wits above.

Donald E. Marlatt P.S. #18660 in 1982, 1990 & 1992 fnd. 1/2" bar & marked wits: (S 15° E 13" Pine stp. 6.35') (old NBT), (S 40° E 10" Oak 29.0') (N 27° W 12" Oak 24.0' Ex. NBT) (N 20° E 11" Oak 10.2') Ex. NBT; Survey Rec. L. 3, P. 563, Montmorency Co. Rec's.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(A-12) Fnd. 1/2" bar & wits by Marlatt (No I.D. cap).  
(Re-placed 1/2" bar with 4" dia. Conc. Mon. and 3" dia. Aluminum cap #18654 marked Montmorency Co. Re-Mon. Corner.



**C. Description of monument for corner and accessories established to perpetuate locating the position of:**

(A-12) 1/4 Cor. Comm. to Sec. 36, T29N, R1E & Sec. 31, T29N, R1E  
4" x 36" Conc. Mon. & Re-Mon. cap #18654. Accepted as the best available evidence of the re-establishment of the original Corner, approved by the Peer Group on September 24, 1993.  
S 55° E 29.28' 12" B. Oak S 20° E 6.32' 12" J. Pine (dead)  
N 50° W 25.56' 5" Norway Ex. Aluminum tag by Henning (old NBT)  
S 85° W 53.86' 7" Norway N 15° E 10.18' 10" Oak (dead)  
S 35° W 95.78' 15" W. Oak (old NBT)  
(Placed blaze, 20 penny spike & P.S. tag #18654) (typ)

Signed by Larry G. Beauregard Date 12-27-93  
Surveyor's Michigan License No. 18654