

Montmorency County Remonumentation

Liberal 12 Page 50

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

08346

For corners in

Montmorency (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>29N</u> R <u>1E</u>	<u>A-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED
MONTMORENCY COUNTY
REGISTER OF DEEDS
DEC 28 9 05 AM '93

A. PANGLOSS-KELSOY

Register of Deeds Stamp & File Number

I, Larry Beauregard, in a field survey on October, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- (A-13) A. Description of original monument and accessories and/or subsequent restoration:
- GLO- May 1839 John Hodgson
Mon.- Post
Wit: 7" B. Oak N 13° W 50 links
9" B. Oak S 61½° E 64 links
June 1921 Pg. 155 Co. Surveyor
Mon.- Conc. post set
G.F. De La Mater 1926 fnd. Cedar post & older post.
Wits: B. Oak 8" N 69 W 35.5'
Y. Pine 24" S 10° E 134.0'
 - Consumers Power Co. Mar. & Oct. 1967
Mon.- fnd. ½" bar
Wit: 10" N. Pine S 65° E 105.60'
8" J. Pine N 45° E 118.30'
24" Pine Stump S 10° E 134.00'
Concrete Post SW 57.30'
 - Norman C. Caldwell 1968
Mon.- fnd. ½" bar
Wit: 10" N. Pine S 65° E 105.60'
24" Pine Stump S 10° E 134.00'
8" J. Pine N 45° E 118.30'
 - George D. Henning P.S. #2240 in 1964
Iron fnd. (De La Maters Corner.) Wits fnd:
10" Norway S 65° E 105.6' (1964)
24" Norway N 38° E 134.0' (stump) G.F.D.
14" B. Oak N 38° W 113.5' (1964)
8" J. Pine N 45° E 118.3' (1964)
 - Larry G. Beauregard (Scott Assoc. Inc.) 1986
L. 249, Page 163, P.S. #18654
Mon.- 1" bar
Wit: 20" N. Pine S 65° E 105.60'
12" J. Pine N 45° E 118.30'
24" Pine Stump N 11° E 134.00'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-13) Fnd. ½" bar in mon. box C/L of Rd. intersection N - E - S & W.
(Placed Montmorency Re-mon. cap on same. P.S. #18654).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-13) Fnd County corner comm. to Crawford, Otsego, Montmorency, & Oscoda counties, NE Cor. Sec. 1, T28N, RLW, Sw Cor. Sec. 36, T29N, RLW, Nw Cor. Sec. 6, T28N, R1E & the SW Cor. of Sec. 31, T29N, R1E. ½" bar in Mon. box with 3" dia. cap marked Montmorency Re-Mon. Cor. Accepted as a perpetuation of the original government corner, approved by the Peer Group on September 24, 1993.
S 64° E 122.05' U.S. Army BM Mon. with brass cap.
S 57° E 105.38' 15" Norway (R) NBT
S 23° W 119.25' 3" Norway
N 36° W 119.55° 8" Norway
(Placed blaze 20 penny spike & P.S. #18654) (typ)

Signed by Larry G. Beauregard Date 12-27-93
Surveyor's Michigan License No. 18654
Revised 2-2-94 L.B.

