

MAY 1 1997

Montmorency County Remonumentation

Liber 00012 Page 0227

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MONTMORENCY
(County)

Located In: ALBERT TWP. Corner Code ##

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

11-06-1996 11:06:34

A. PANGAN-MCELROY
REGISTER OF DEEDS

- 1. Public Land Survey T 29N R 1E D-1
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, **FREDERICK J. KING**, in a field survey on May 29, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-1 - NORTH 1/4 CORNER OF SECTION 5

Not set on Original Government Survey

Date ? - F.W. Smith #754 - Don Marlatt, P.S.#18660 provided map of area, indicating that Smith had worked in area and Peer Committee felt that he had set this corner.

No Act 74 Found Recorded for this Corner
No Act 132 Found Recorded for this Corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-1 - NORTH 1/4 CORNER OF SECTION 5

Found Axle Shaft @ Corner D-1

West - 49.02' - Found Conc. Mon. @ Corner D-13 (T30N-R1E)
S05°E - 66.15' - Found Spk N side of 12" J. Pine
N80°W - 41.85' - Found Spk S side of 10" J. Pine
Corner D-1 is ±42' N of C.L. E-W trail & ±30' W of N-S trail.

This Corner approved by County Peer Review on June 7, 1996, as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1 - NORTH 1/4 CORNER OF SECTION 5

Placed Montmorency County Re-Mon Cap on found Axle Shaft

S40°E - 25.51' - NW face of NW Steel Post of Manhole Corral
S05°E - 66.63' - Set S&T E side of 12" J. Pine
N80°W - 42.00' - Set S&T above found Spk - S side of 10" J. Pine
N05°W - 19.62' - Set S&T E. side of 5" Poplar
Corner is ±42' N of E-W trail & ±31' W of N-S trail
West - 49.02' - Corner D-13 (30-1)



Signed by

Frederick J. King

Date October 24, 1996

Surveyor's Michigan License No. 25852

JUN 07 96

L.H.B.