

JAN 28 1999

Liber 00012 Page 0336

Montmorency County Remonumentation

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

12-07-1998 09:38:30

MARY JO GUEST
REGISTER OF DEEDS

For corners in

<u>MONTMORENCY</u> (County)	Located In:	Corner Code #
ALBERT TWP.	T 29 N R 1 E	E - 3
1. Public Land Survey	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

I, DONALD E MARLATT, in a field survey on MAY, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3					8								
4	7						9			10		11	12
5													
6	18									15		14	13
7													
8	19									22		23	24
9													
10	30									27		26	25
11													
12	31									34		35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:
E - 3 CORNER COMMON TO SEC.'S 4-5-8 & 9.
GLO CORNER SET LEWIS CLASON IN APRIL 1840.
SPR. PINE 9" N71W 27 L.- SPR. PINE 10" S69°E 39 L.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
E - 3 CORNER COMMON TO SEC.'S 4-5-8 & 9.
FOUND NO EVIDENCE OF CORNER.
SET CORNER BY DOUBLE PROPORTION.

APPROVED BY
PEER GROUP

JUL 28 98

L.S.B.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E - 3 CORNER COMMON TO SEC.'S 4-5-8 & 9.
SET CONC. MONUMENT AND REMON. CAP.
S 78°W 12" J. PINE 22.47'
S 27°W 7" J. PINE 14.78'
S 75°E 8" J. PINE 11.27'
N 55°E 11" J. PINE 15.40'



WITNESSES MARKED WITH 40 PENNY SPIKES AND P.S. TAGS#18660
APPROVED BY PEER GROUP ON JULY 28, 1998 AS A CAREFUL AND FAITHFUL ESTABLISHMENT OF
THE POSITION OF THE CORNER.

Witnessed by Donald E Marlatt
Surveyor's Michigan License No. 18660

Date 12/4/1998