

JAN 28 1999

Montmorency County Remonumentation

Liber 00012 Page 0339

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MONTMORENCY

(County)

ALBERT TWP.

1. Public Land Survey

Located in:

Corner Code #

T29N R1E

E-6

T R

T R

T R

S T R

S T R

S T R

S T R

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. , Recorded Plat

5. Private Claims

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

12-07-1998 09:38:59

MARY JO GUEST
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, DONALD E MARLATT, in a field survey on MAY, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-6 1/4 CORNER COMMON TO SEC. 'S 16 & 17.
GLO COR. SET LEWIS CLASON IN APRIL 1840. SPR.PINE 10" S57°E 43 L.-SPR.PINE 7" N73°W 23 L.
SURVEY BY L. BEAUREGARD RLS#18654 IN 1-16-1976. SET 1/2"BAR & RLS CAP BY S.P. WIT.
N80°W 13.7' 8"J.PINE-N20°W 25.55' 6"J.PINE-S20°W 24.95' 6"J.PINE.
ACT 74 BY L. BEAUREGARD 1-16-1976.(SAME AS ABOVE)
SURVEY D.E.MARLATT RLS#18660 8/10/1981. FOUND 1/2"BAR & CAP#18654. N80°W 13.7' 9"J.PINE
N20°W 25.55' 7"J.PINE-S20°W 24.95' 6"J.PINE.
SURVEY BY DAN SCHRIPEMA RLS#24617 7/6/1989. L.3, P.558. FOUND 1/2"BAR & CAP. WIT.
N80°W 13.7' 8"J.PINE-N20°W 25.55' 6"J.PINE-S20°W 24.95' 6"J.PINE.
SURVEY BY D.E.MARLATT 10-1-1996. L. 10004, P.424. FOUND 1/2"BAR & CAP#18654. NO WIT.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-6 1/4 CORNER COMMON TO SEC. 'S 16 & 17.
FOUND 1/2"ROD & CAP# 18654.
WIT. N80°W 13.7' 9"J.PINE-N20°W 25.55' 7"J.PINE-S20W 24.95' 6"J.PINE.(ALL 3 WIT. DEAD)


C. Description of monument for corner and accessories established to perpetuate location of the corner:

E - 6 1/4 CORNER COMMON TO SEC.'S 16 & 17.
SET CONC. MONUMENT & REMON. CAP.
S75°W 8"J.PINE 5.94'
S34°E 9"J.PINE 8.97'
N70°E 8"J.PINE 14.50'
N20°E 6"J.PINE 13.69'

APPROVED BY
PEER GROUP

JUL 28 98

D.E.B.



WITNESSES MARKED WITH 40PENNY SPIKES & P.S. TAG #18660.
APPROVED BY PEER GROUP ON JULY 28, 1998 AS A CAREFUL AND FAITHFUL ESTABLISHMENT OF THE POSITION OF THE CORNER.

Signed by Donald E Marlatt

Date 12/4/1998

Surveyor's Michigan License No. 18660