

JAN 28 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MONTMORENCY CO.
(County)

Located In: Corner Code #

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

12-07-1998 09:39:18

MARY JO GUEST
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1. Public Land Survey	T	29N	R	1E	E-8
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, DONALD E MARLATT in a field survey on MAY, 1998
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-8 1/4 COR. COMMON TO SEC.'S 20 & 21
GLO CORNER SET LEWIS CLASON IN APRIL 1840. SPR.PINE 5"S56°W 22 L., SPR.PINE 8" N46°E 20 L. SURVEY BY G. HENNING RLS#2240 IN MAY 1965. FD. AXLE SHAFT & WIT. BT 6"J.PINE S45°E 6.1'TAG. BT 14"J.PINE N 3°W 18.7' TAG-BT 10"J.PINE S51°W 4.5'TAG- CORNER SET BY FRANK SMITH RLS# 754. SURVEY BY L. BEAUREGARD OCT. 1970. RLS #18654. SURVEY BY L. BEAUREGARD 10-28-80. FD. AXLE SHAFT. WIT. S45°E 6.1' 6"J.PINE(R) S51°W 4.5' 10"J.PINE(R)-N 3°W 18.7' 14"J.PINE(R) RLS#18654.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-8 1/4 COR. COMMON TO SEC.'S 20 & 21,
FOUND AXLE SHAFT,
WIT. BT 6"J.PINE S45°E 6.1' - BT 14"J.PINE N 3°W 18.7' - BT 10"J.PINE S51°W 4.5'.
FOUND 1/2"ROD BY G, HENNING RLS#2240 33' WEST.

APPROVED BY
PEER GROUP

JUL 28 98

D.E.B.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E - 8 1/4 COR. COMMON TO SEC.'S 20 & 21.
SET CONC. MONUMENT WITH REMON. CAP.
N57°W 10"OAK 21.38'
S87°W 10"W.PINE 15.77'
S30°W 14"OAK 15.50'
S 3°E 20"OAK 27.06'



WITNESSES MARKED WITH 40 PENN SPIKES & P.S. TAG#18660
APPROVED BY PEER GROUP ON JULY 28, 1998 AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by Donald E Marlatt

Date 12/4/98

Surveyor's Michigan License No. 18660