

**SURVEY &  
REMONUMENTATION**  
Montmorency County Remonumentation

DEC 18 1995

Liber **00012** Page **0163**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

STATE OF MICHIGAN  
MONTMORENCY COUNTY  
Recorded & Filed

11-14-1995 10:16:25

A. PANGAH-MCELROY  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

<u>MONTMORENCY</u> (County)	Located In:	Corner Code #/
	<b>ALBERT TWP.</b>	
1. Public Land Survey	T <u>29</u> N R <u>1E</u>	F-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, **Frederick J. King**, in a field survey on **May 3, 1995**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

F-1 - NORTH 1/4 CORNER, SECTION 4

Not Set on Original Government Survey  
No Recorded Act #132 Found  
No Recorded Act #74 Found

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-1 - NORTH 1/4 CORNER SECTION 4

Found Axle Shaft - ± 8 1/2' N. of E-W 2-track  
West - 28.53' - Fnd Conc Mon. @ Cor. F-13, T30N-R1E  
Meas from E-1 to F-1 = 2622.94'  
Meas from F-1 to G-1 = 2621.93'

**APPROVED BY  
PEER GROUP**

JUN 02 95

*JLB*

This Corner Approved by Peer Review Committee on June 2, 1995 as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1 - NORTH 1/4 CORNER SECTION 4

Set County Re-Mon Cap on Fnd Axle Shaft  
S.70°E - 88.78' - Set Tag N side 10" Oak  
S.10°W - 46.95' - Set Tag W side 10" Oak  
N.75°W - 53.58' - Set Tag S side 15" Oak  
N. 5°W - 81.80' - Set Tag W side 10" Oak  
South - 30' - Set 2"x4" Treated Stake  
Corner is ± 8 1/2' N of C.L. of E-W 2-track  
Corner F-13 is 28.53' W of Corner F-1  
Set 2"x4" Treated Stake 30' South of Corner F-1



Signed by *Frederick J. King*

Date 10-30-95

Surveyor's Michigan License No. 25852