

For corners in

Montmorency Located In: Albert Twp. Corner Code #
 (County)

1. Public Land Survey T 29N R 1E F-3
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____
 T _____ R _____

3. Miscellaneous S _____
 T _____ R _____
 Property in Sec. S _____
 T _____ R _____

STATE OF MICHIGAN
 MONTMORENCY COUNTY
 Recorded & Filed

08-25-1998 11:08:19

MARY JO GUEST
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Montmorency County Remonumentation

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3					●								
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Larry G. Beauregard, in a field survey on April, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-3 Corner Common to Section 4 & 9, T29N R1E.

1939 - Lewis Clason D.S. - BK. Oak 6" used for 1/4 Sec. Post. No wit's mkd.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

April 1998 - Fnd. no evidence of 6" BK Oak for Cor. Set 3 1/2" Aluminum Re-mon cap on 4" dia. x 36" concrete monument on Sec. line by single Proportion.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-3 Corner Common to Sections 4 & 9, T29 R1E

3 1/2" aluminum Re-mon cap on 4" dia. x 36" concrete monument. Accepted as a careful and faithful establishment of the position of the Corner. Approved by the Peer Group on July 28, 1998.

S56E	30.24'	14"Oak	(Placed blaze 60d spike & PS tag#18654)(Typ.)
S40W	22.42'	15" "	" " " " " " " "
N78W	29.28'	12"Oak	" " " " " " " "
N05E	25.50'	12"Oak	" " " " " " " "

Signed by Larry G. Beauregard
 Surveyor's Michigan License No. 18654

Date 8-24-98

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL

SURVEYORS, JAN 28, 1971 REVISED MAY 14, 1975
 REVISED JAN, 1983 REVISED OC, 1985

SURVEY &
 REMONUMENTATION

OCT 08 1998

SECTION



APPROVED BY
 PEER GROUP

JUL 28 98

L.B.B.