

FEB 06 1998

Montmorency County Remonumentation Liber 00012 Page 0281

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MONTMORENCY (County) ALBERT TWP.	Located In:	Corner Code #
1. Public Land Survey	T 29N R 1E	I - 10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
MONTMORENCY COUNTY  
Recorded & Filed

12-16-1997 10:51:04

A. FANGAN-MCELROY  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, DONALD E MARLATT, in a field survey on 6/12, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I - 10 1/4 COR. COMMON TO SEC.'S 26 & 27  
 GLO CORNER SET BY LEWIS CLASON-APRIL 1840. Y.PINE 9"-S38°E-33 L,W.PINE 7"- N43°W- 33 L.  
 F. SMITH NOTES- 9-13-43. IRON POST-CEMENT-MON. S44°W-47.95',N.PINE 10"-N42°W-52.4'.  
 FOREST PARK SUB. BY F. BATEMAN 9-3-46. L. 1, P. 70.  
 SURVEY BY S. THORSEN 6-9-54. FD 1/2"BAR.  
 AVID JOHNSON'S SUB. #2 BY S. THORSEN 12-6-63. L. 2 OF PLATS, P. 45.  
 SURVEY BY N.C. CALDWELL 9-3-1970. MONTMORENCY CO. RD. PLANS DATED 6-11-91.  
 SURVEY BY R.S.SCOTT ASSO. INC. 4-14-95. 1/2" ROD IN MON. BOX  
 FD. 1/2"BAR IN MON. BOX. L. 10004, P. 254. WEST 37.78' 10"J.PINE  
 N50°E 44'-P.POLE N50°W 52.47' 14"J.PINE  
 S50°W 49.93'-CONC. MON. N50°E 44.05' T. POLE  
 S30°E 60.63' 7"N.PINE  
 S88°W 37.71' 9"N.PINE

B. Description of corner evidence found and / or method applied in restoring or reestablishing corner.

I - 10 1/4 COR. COMMON TO SEC.'S 26 & 27. FD. 1/2"ROD AND CAP#19237 IN MON. BOX.  
 N39°W 18"N.PINE 52.55' (CO.)  
 S88°W 13"N.PINE 37.70' (SCOTT) (CO.)  
 S33°E 10"N.PINE 60.75' (SCOTT)  
 N55°E P.POLE 44.03' (SCOTT) (CO.)

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I - 10 1/4 COR. COMMON TO SEC.'S 26 & 27.  
 PLACED REMON. CAP ON 1/2" ROD IN MON. BOX.  
 N39°W 18"N.PINE 52.55'  
 S88°W 13"N.PINE 37.7'  
 N72°E 12"MAPLE 53.06'  
 S33°E 10"N.PINE 60.75'  
 N55°E P.POLE 44.03'

APPROVED BY  
PEER GROUP

JUN 20 97

*L.E.B.*



WITNESSES MARKED WITH 40 PENNY SPIKES AND P.S. TAGS #18660.  
 APPROVED BY PEER GROUP JUNE 20, 1997 AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Recorded by Donald E Marlatt Date \_\_\_\_\_  
 Surveyor's Michigan License No. 18660