

FEB 06 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**
MONTMORENCY

(County)	Located in:	Corner Code #
ALBERT TWP.	T <u>29N</u> R <u>1E</u>	<u>I - 12</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

12-16-1997 10:53:38

A. PANGAN-MCELROY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, DONALD E MARLATT, in a field survey on 7/4, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I - 12 1/4 COR. COMMON TO SEC.'S 34 & 35
GLO COR. SET BY LEWIS CLASON APRIL 1840. SPR PINE 12"-S28E-27 L, W. PINE 9"-N42°W 37 L.
FRANK SMITH NOTES-G. STEVENS 8-3-1934, Y. PINE 10"-N56°45'W 72.1', Y. pine 10"-N46°30'E- 73'
PLAT OF GOV'T LOT 1 BY FRANK SMITH-NO DATE. SURVEY BY S. THORSEN AUG. 6, 1956.
ACT 74 BY N.C. CALDWELL 8-7-1997-L. 1, P. 18. FD 1/2"BAR. WIT. N15°E 15.8' 4"PIPE
SURVEY BY N.C. CALDWELL 3-10-73. L. 1, P. 316. N47°E 73.0' 10"Y. PINE
SURVEY BY R.S. SCOTT ASSO. INC. 7-17-91. L. 4, PAGE 6. FD. 1/2"BAR. N57°W 72.1' 10"Y. PINE
MONTMORENCY COUNTY RD. COMMISSION PLANS. 6-11-91. S84°W 88.4' 10"Y. PINE
S45°E 67.28' 7"W. PINE., N30°E 53.45' T. POLE
S25°W 62.45' T. POLE. (SURVEY BY D.R. MAC NEILL).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I - 12 1/4 COR. COMMON TO SEC.'S 34 & 35
FD. ROD & CAP#19237 IN MON. BOX IN SOUTH CURB
N72°E ANCHOR POLE 87.15' P.S. TAG#19237
S30°E 12"W. PINE 67.45'

VERIFIED POSITION FROM N.C. CALDWELL SURVEY L. 1, P. 18. ALSO FOUND 2 STUMPS THAT WOULD MATCH CALDWELL'S WITNESSES.

NO EVIDENCE OF ORIGINAL COR.


Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I - 12 1/4 COR. COMMON TO SEC.'S 34 & 35
PLACED CAP # 18660 ON EXISTING BAR IN MONUMENT BOX.
N73°W 18"N. PINE 86.70'
N72°E ANCHOR POLE 87.15'
N47°W 12"N. PINE 101.03'
S30°E 12"W. PINE 67.45'

**APPROVED BY
PEER GROUP**

JUL 11 97

D.E.B.



WITNESSES MARKED WITH 40PENNY SPIKES & P.S. TAGS # 18660
APPROVED BY PEER GROUP JULY 11 AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

signed by Donald E Marlatt

Date 12/15/1997

Surveyor's Michigan License No. 18660