

FEB 06 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Form with fields for County (MONTMORENCY), Located In (ALBERT TWP.), Corner Code (#), and numbered items 1-5 for Public Land Survey, Property Controlling, Miscellaneous, Lot No., and Private Claims.

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

11-12-1997 09:40:56

A. PANGAN-MCELROY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, FREDERICK J. KING, in a field survey on June 12, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-10 - 1/4 CORNER COMMON TO SECTIONS 25 & 26

- June 1840 - Original Post set by L. Clason, D.S. (Pg 356) \* N27W-22 1k(14.52')6" Spr P. \* S42E-29 1k(19.14')15" J. Pine
Apr. 1968 - Act 132 by N.C. Caldwell, PS #12018 - No Cor Desc - No Wit - Not Recorded - (Set Post thru Ice)
May 1972 - Act 132 by G.D. Henning, PS #2040 - Indicates Corner Marker was found in "BIG WOLF LAKE" - Set 1/2" Iron Bar & Stake 36.9' North of Corner on High Ground and on Section Line.
Jan. 1976 - Act 132 by L.G. Beauregard, P.S.#18654 - Shows 1/2" I.C. Set - No Wit. - Not Recorded.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-10 - 1/4 CORNER COMMON TO SECTIONS 25 & 26

Found Record G.D. Henning Iron & Cap #2240 with Broken Concrete Mon alongside Record Witnesses Found - None

APPROVED BY
PEER GROUP

JUN 20 97

J.Y.B.

This Corner Approved by County Peer Review on June 20, 1997, as the best available evidence of the position of the Original Corner, as related to the Reference Monument

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10 - 1/4 CORNER COMMON TO SECTIONS 25 & 26 as Related to Ref. 5

- Placed Concrete Monument & County Re-Mon Cap @ G.D. Henning 1/2" Iron Location - (Removed Broken Mon)
Corner K-10, is now in Big Wolf Lake, therefore, Mon & Cap now set, is a "REFERENCE CORNER" to said K-10 and is 36.90' North of said K-10
N10E - 30.91' - Set S&T on E side of 15" Oak
N45E - 7.62' - Set S&T on NW side of 10" R. Pine
S40W - 37.92 - Set S&T on N side of 18" R. Pine
N55W - 15.30' - Set S&T on NE side of 8" Oak
SOUTH- 36.90' - Dipped CORNER K-10, in Water of Big Wolf Lake - Not able to tell what is at Corner.

Signed by Frederick J. King

Date Nov. 6, 1997

Surveyor's Michigan License No. 25852

