

**SURVEY & REMONUMENTATION**

FEB 06 1998

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

<u>Montmorency</u> (County)	Located In:	Corner Code #
	Albert Township	
1. Public Land Survey	T 29N R 1E	L-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
 MONTMORENCY COUNTY  
 Recorded & Filed

10-17-1997 11:40:38

A. PANGAN-MCELROY  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Larry G. Beauregard, in a field survey on May 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

L-9 1/4 corner for Sections 24 & 25.

Aug. 1840- Lewis Clason D.S., Set Qr. Sec. post. Wit's mkd: (Spr. Pine 8" N 52° W 21 lks) (Spr. Pine 12" S 62° E 43 lks). No date- Frank N. Smith P.S. #754, Most likely set or fnd. pipe. (No field notes to support same). Co. Rd. map indicates he was along section line.

July 1966 & MAY 1972- George D. Henning P.S. #2240, Fnd. pipe for corner in a section divisional survey of Sections 24 & 25. No wit's mkd.

April 1971 thru 1995- Larry G. Beauregard P.S. #18654, Fnd. pipe at corner 18" below Rd. surface & raised with 1/2" bar & cap in a section divisional survey of Section 25. Cert. of Sur. Rec. L. 4, P. 482. Wit's mkd. on Co. Rd. survey 1995. (N 40° W 124.60' P. Pole) (S 25° E 80.33' J. Pine) (S 60° W 88.56' 5" Oak) (South 40' bar & cap

**B. Description of other evidence found and/or method applied in restoring or reestablishing corner:**

Fnd. 1/2" bar & cap 3' North of Rd. c/1.

Placed Co. Re-mon. cap on same. Mon box will be placed later on Rd. construction in 1998.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

L-9 1/4 corner for Sections 24 & 25.

1/2" x 18" Bar & Re-mon cap Accepted as the best available evidence of the position of the original corner. Approved by the Peer Group on June 20, 1997.

N 40° W 124.60 P. Pole (PK nail & P.S. Tag #18654)

S 25° E 80.33' 8" J. Pine

South 40.0' Ex. 1/2" Bar & Cap #18654

S 60° W 88.56' 5" Oak

Placed 60d penny spike P.S. Tag #18654 & Blaze (typ)

APPROVED BY  
 PEER GROUP

JUN 20 97 *J.G.B.*



Signed by Larry G. Beauregard  
 Surveyor's Michigan License No. 18654

Date 10/17/97