

# SURVEY & REMONUMENTATION

APR 24 1995

## Montmorency County Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 00012 Page 0127

### COMMISSION

For corners in

<u>Montmorency</u> (County)	Located In: Albert Township	Corner Code # <u>K-13</u> <u>L-13</u> ✓
1. Public Land Survey	T <u>29 N</u> R <u>1 E</u>	
	T <u>29 N</u> R <u>1 E</u>	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	<b>APPROVED BY PEER GROUP</b>
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	<b>MAY 13 94</b> <i>JB</i>
	S _____ T _____ R _____	

STATE OF MICHIGAN  
MONTMORENCY COUNTY  
Recorded & Filed

11-10-1994 14:12:14

A. PANGAN-MCELROY  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Don Marlatt, in a field survey on November 8, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therelore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- |   |   |
|---|---|
| (K-13) South Cor. common to Secs. 35 & 36, T 29 N, R 1 E<br>Post set by Lewis Clawson Dec. 1839.<br>8" Spr. Pine N 24° W 40 links<br>20" J. Pine N 56° E 47 links<br>N. Caldwell - Survey - L. 1, P. 399.<br>R.S. Scott Engineering - Survey - 1-18-1974.<br>R.S. Scott Engineering - Survey - L. 4, P. 83. | (L-13) S. 1/4 Cor. Sec. 36, T 29 N, R 1 E<br>Post set by Lewis Clawson Dec. 1839.<br>6" Spr. Pine N 34° W 53 links<br>6" Spr. Pine N 37° E 21 links<br>R.S. Scott Engineering - Survey - 1-18-1974. |
|---|---|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- |   |  |
|---|--|
| (K-13) South Cor. common to Secs. 35 & 36, T 29 N, R 1 E<br>Found 2" pipe in concrete base.<br>N.W. Cor. Sec. 1, 28/1, 7.92' West.<br>No evidence of original corner.<br>Accepted as the best available evidence of the reestablishment of the original corner. | (L-13) S. 1/4 Cor. Sec. 36, T 29 N, R 1 E<br>Found 1" pipe & square Oak stake.<br>N. 1/4 Cor. Sec. 1, 28/1, 4.71' West.<br>No evidence of original corner.<br>Accepted as the best available evidence of the reestablishment of the original corner. |
|---|--|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |  |   |
|--|---|
| (K-13) South Cor. common to Secs. 35 & 36, T 29 N, R 1 E<br>Placed Remonumentation Cap in 2" pipe in concrete.<br>7" J. Pine S 70° W 32.3'<br>15" J. Pine S 30° W 29.58'<br>11" J. Pine S 1° W 30.78'<br>12" Oak S 89° E 69.2'<br>10" J. Pine N 9° W 42.4' | (L-13) S. 1/4 Cor. Sec. 36, T 29 N, R 1 E<br>Set concrete monument & placed Remonumentation Cap.<br>10" J. Pine N 21° E 26.12'<br>10" R. Pine N 89° E 33.74'<br>15" R. Pine S 23° E 49.27'<br>14" J. Pine S 3° W 32.63' |
|--|---|

Witnesses marked with a 30 penny spike & I.D. tag #18660.

Signed by Donald E Marlatt

Date 11-9-1994

Surveyor's Michigan License No. 18660

