

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Montmorency (County)	Located In	Corner Code #
1. Public Land Survey	T <u>29N</u> R <u>1E</u>	<u>B-8</u>
	T _____ R _____	_____
2. Property Controlling in Section	S <u>19</u> T <u>29N</u> R <u>1E</u>	<u>9</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on May 20, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	15		17		16		18		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-8 Norman C. Caldwell RLS #12018 Cert. of Survey 1970. Used center of section 19 no description of corner material. 9- Norman C. Caldwell RLS #12018 Cert. of Survey April 1970 placed 1/2" bar with cap no witnesses given.

Norman C. Caldwell RLS #12018 subdivision plat "West Town Mobile Home Estates" L.2 P. 86 and 87 shows tie to center of section 19 no description of corner material.

Donald E. Marlatt RLS #18660 L. 4 P. 85 Cert. of Survey Nov. 1992 Found concrete monument. Wit: S10°W 12" Oak 2.65', N40°W 12" oak 32.75', N15°E 12" Oak 29.41', East 15" Oak 22.65'.

Frederick J. King P.S. 25852 L. 4 P. 481 Cert. of Survey May 1997 Shows tie to found iron in concrete at the center of section 19.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

B-8 Found 4" concrete monument fitting Norman C. Caldwell's 1970 Certificate of survey. 9- Found 1/2" bar with Cap RLS #12018 fitting Norman C. Caldwell's 1970 Certificate of survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-8 Found 4" concrete monument Wit: 10" Oak N37°W 33.11' 5" Oak N47°E 41.83' 12" Oak S49°E 31.92' 10" Oak S28°W 3.14' Carsonite Post North 1'±	9- Found 1/2" bar with cap RLS #12018 Wit: 20" Oak S13°W 6.71' 5" Maple N84°E 27.54' 10" Oak North 22.56' 8" Oak N65°W 25.28' Carsonite Post North 1'±
---	--

Signed by: Carl T Kiiskila
 Surveyor's Michigan License No.: 33981

Date: 1-15-02

