

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 29 NR 2 E
T 30 NR 2 E

Montmorency COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 35 and 36
on south boundary of T30N, R2E

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

7" Aspen - N47W - 24 links

8" B. Oak - N33E - 24 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

This corner was found by Forestry Division Land Surveyor while making a survey in this area. Found old post on ground about 22 links west of closing corner. Stumps in approximate locations for government BTs. Corner was noted by F. Smith in 1941. Appears acceptable as best available evidence.

Closing corner to Sections 1 and 2, T29N, R2E is 22 links east.

Corner was placed and witnessed June 24, 1960.

SURVEYORS SEAL

SIGNED

REGISTERED LAND SURVEYOR

DATE 7/6/60