

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 29 N. R. 2 E.	K-11;L-11;M-10;M-11
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 20, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories used for subsequent restoration:~~

C. (continued)

M-11
Left conc. mon. in place
10" Cedar N62°E 45.2
8" Cedar S26°E 48.8

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-11 Set corner from Stevens witnesses to a previous corner, which is either buried very deep or removed in road construction.
- L-11 Found concrete monument as previously restored in Stevens 1940 road survey.
- M-10 Found concrete monument as restored by Stevens in road survey in 1940.
- M-11 Found concrete monument as restored by Stevens in 1940 road survey, at road intersection.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-11	L-11	M-10
Set 1"x30" pipe below surface	Left conc. mon. in place	Left 4" conc. mon. in place
8" Cedar S58°E 39.0	14" R. Pine N68°E 59.6	9" Spruce S80°W 77.0
10" Cedar S30°W 23.9	9" Tamarack N73°W 112.2	2" Balsam N50°E 23.0
	14" Boulder South 32.2	

SIGNED BY *Kenneth J. Ostling* DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

