

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 29 N. R. 2 E.	E-1; E-3; G-1; H-1
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 30, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A--Description of original monument and accessories and/or subsequent restoration:

C. (continued)

	H-1
Set DNR mon. & red-top post	
7" Oak	S52°E 26.4
10" Oak (top gone)	
	S83°E 16.85

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-1 Found 4" concrete monument in place, probably established by G. F. DeLaMater. SW corner Sec. 33, T. 30 N., R. 2 E., is 13.2' west.
- E-3 Set this corner on line and double distance over good ¼ and section corner east. Nothing found for previous corner.
- G-1 Found concrete monument as previously established by G. F. DeLaMater survey. SW corner Sec. 34, T. 30 N., R. 2 E., is 19.1' west.
- H-1 Restored this corner in position as previously established, possibly by DeLaMater. Monument had been removed from edge of gravel pit. Appears to have been used in control of plat and other parcels in Sec. 3.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1	E-3	G-1
Left 4" conc. mon. in place set cedar post	Set DNR mon. & red-top post	Left conc. mon. in place set cedar post
22" R. Pine S25°W 9.9	3" R. Pine S04°W 61.35	8" R. Pine S30°W 5.6
12" Oak N83°E 30.0	6" R. Pine N74°E 26.95	9" Oak S45°E 62.85
R.Pine stump S77°E 18.55 (old face)		Conc. Mon. S45°E 50.0
		Conc. Mon. S45°W 65.1
		12" W. Oak (DeLaMater) S35°W 73.0

SIGNED BY Kenneth J. Ostling DATE 7/15

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____ MONTMORENCY COUNTY

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET