

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 29 N. R. 2 E.	B-1;C-1;D-3;G-3;I-2
2. PROPERTY CONTROLLING IN SECTION	T. N. S., R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S., R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER _____

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 9, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A - ~~Description of original monument and accessories and/or subsequent restoration~~
 C. (continued)

G-3	I-2
Set DNR mon. in place of	Set DNR monument & red-top post
½" rebar w/RLS cap (12018)	4" Tw. W. Pine N60°E 47.7
24" Oak S69°W 40.4	4" J. Pine N32°W 65.35
23" Oak N30°W 13.35	½" Rerod N03°E 16.33
16" Pine Stump (OBT)	
West 12.9	

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-1 Set corner by proportionate measurement between section corners.
- C-1 Set corner U.S. record east of standard corner. No original evidence.
- D-3 Set corner by proportionate measurement between section corners; nothing for previous corner.
- G-3 Fd. ½ iron bar at corner, replaced w/DNR monument; corner previously restored from U.S.B.T. stump.
- I-2 Set corner to conform with E-W ½ line as previously estab. in interior subdivision for plat of Avery Lake South Shores.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1	C-1	D-3
Set DNR monument	Set DNR mon. & cedar post	Set DNR mon. & cedar post
20" W. Oak S37°E 93.65	8" Maple N15°W 1.6	4" R. Pine N56°W 46.2
8" Maple S78°E 40.5	8" Basswood S32°W 40.2	11" Oak S05°W 18.7
½ Sec. 31 T30N-R2E	SE corner Sec. 31 T30N-	
West 6.6	R2E West 6.6	

SIGNED BY *Kenneth J. Ostling* DATE 11/13/77

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

ALBERT TOWNSHIP
 MONTMORENCY COUNTY

