MAY 1 8 1997

Montmorency County Remonumentation iber 00012 Page 0232

COMMISSION

5. Private Claims

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN MONTMORENCY COUNTY


Register of Deeds Stamp & File Number

For corners in Recorded & Filed MONTMORENCY Located In: Corner Code ≠ ALBERT TWP. 11-06-1996 11:07:18 T _29N R _2E__ E-13 **Public Land Survey** A. PANGAN-MCELROY T _____ R __ T _____ R __ REGISTER OF DEEDS T _____ R __ _ T ____ R _ 2. Property Controlling ___ T ____ R _ S. in Section __ T .____ R _ Miscellaneous S T R ... Property in Sec. _____, Recorded Plat _

I FREDERICK J. KING , in a field survey on May 30 ___ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land

Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.



A. Description of original monument and accessories and/or subsequent restoration:

E-13 - CORNER COMMON TO SECTIONS 32 & 33 (Cor E-1 (28-2) Intersected 64 lks (42.24') E of E-13

Dec. 1839 - Original Post set by Clason, Dep. Sur. - N22°W - 27 lks (17.82') - 10" SprPi N46°E - 36 1ks (23.76') - 11" SprPi

Cor E-1 July 1970 - Act 74 (L2, P281) by K. Ostling #10068 - Set DNR Pipe & Cap @ Remains

of Old Stake Point - Fits E. Houghton Records - Cor E-13 is 41.95' W.

June 1974 - Act 132 (L1, P543) By L. Beauregard #18654 - Used Corner E-13 for survey of St of SWA of SWA of Sec. 33 - Nor Corner Description & No Witness.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13 - CORNER COMMON TO SECTIONS 32 & 33

Found Bent Pipe - No Cap (at N edge of E-W road - Granholm Rd.)

East - 41.95' - Found Rec DNR Pipe & Cap (L2, P281) K. Ostling @ E-1 (28-2)

N35°E- 35.2' - Found Blz 10" Dead J. Pine

S80°E- 54.55' - Found Nail & Tag #22428 (R.Bischer)in S side 20" Oak

S55°W- 92.27' - Found Nail & Tag #22428 in SE side 8" Oak

N200W- 20.38' - Found Nail & Tag #22428 in E side 15" Oak (Also Old Blz)

No Original Government Corner Evidence Found

This Corner Approved by County Peer Review on June 7, 1996, as the best available evidence of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13 - CORNER COMMON TO SECTIONS 32 & 33

Placed Montmorency County RE-Mon Cap & Monument @ found Pipe Position.

N50°E - 40.68' - Set S&T SE side of 6" Oak S80°E - 54.55' - Fnd Tag #22428 - S side 20" Oak

\$550W - 92.97' - Fnd Tag #22428 -SE side 8" Oak \$1000W - 20.38' - Fnd Tag #22428 - E side 15" Oak \$2000W - 20.38' - Fnd Tag #22428 - E side 15" Oak

East -41.95' - Cor E-1 (28-2)

R GROUP Date October 25, 1996

Surveyor's Michigan License No. 25852

96

POFESSION FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. REVISED MAY

OF MICHIGAN

FREDERICK J. KING

ROFESSIONAL SURVEYOR No.

25852