

MAY 16 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

11-06-1996 11:07:40

A. PANGAN-MCELROY
REGISTER OF DEEDS

For corners in

COMMISSION

MONTMORENCY
(County)

Located In: Corner Code #
ALBERT TWP.

- 1. Public Land Survey T 29N R 2E G-13
2. Property Controlling in Section S T R
3. Miscellaneous in Section S T R

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is present in the cell at row 12, column G.

I, FREDERICK J. KING, in a field survey on May 31, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-13 - CORNER COMMON TO SECTIONS 33 & 34 (Cor G-1 (28-2) Intersected 14 lks (9.24') W of G-13)
Dec. 1839 - Original Post set by Clason, Dep. Sur. N150E - 55 lks (36.30') 9" Beech N090W - 57 lks (37.62') 22" B. Oak
Dec. 1970 - Act 74 (Not Rec) by K. Ostling #10068 Set DNR Pipe & Cap @ Old Post Bot Fnd, established in previous sur., possibly by Seeley or Smith. Corner was also located in 1935 Schaaf Sur. N250W - 15.1' - 8" R. Oak N870E - 31.8' - 8" R. Oak Cor G-1 (28-2) is 9.2' West
Cor G-1 Dec 1970 - Act 74 (L2, P324) by K. Ostling #10068 - Set DNR Pipe & Cap @ old Post Bot T28N-R2E as established in previous Sur. by Seeley or Smith. Posts were identified in 1935 Schaaf Sur and appeared to have been accepted as correct.
May 1976 - Act 74 (L1, P164-165) by L. Beauregard #18654 Found Rec DNR Pipe & Cap (L1, P164) N250W - 15.1' - 8" R. Oak N870E - 31.8' - 8" R. Oak Cor G-1 is 9.2' West

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner

- G-13 - CORNER COMMON TO SECTIONS 33 & 34
Found Rec DNR Pipe & Cap (L1, P 164-165) N250W - 15.1' - Fnd Blz in Rec R. Oak N870E - 31.8' - Rec R. Oak GONE West - (M)8.95' (R) 9.2' - Found Rec DNR Pipe & Cap @ Corner G-1 (T28N-R2E)
No Original Government Corner Evidence Found

This Corner Approved by County Peer Review on June 7, 1996, as the best available evidence of the reestablishment of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-13 - CORNER COMMON TO SECTIONS 33 & 34
1" Rec. DNR Pipe & Cap - 4" Aluminum N700E - 14.20' - Set S&T S side of 5" Maple S100W - 15.47' - Set S&T E side of 18" Maple S850W - 23.72' - Set S&T S side of 5" Maple N250W - 15.39' - Set S&T W side of 12" Maple West - 8.95' - Corner G-1 (28-2)



Signed by Frederick J. King APPROVED BY PEER GROUP Date October 25, 1996

Surveyor's Michigan License No. 25852 JUN 07 96

R L.A.B.