

MAY 16 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION

Form with fields for County (MONTMORENCY), Located In (ALBERT TWP.), Corner Code (#) (H-13), and numbered items 1-5 describing survey details.

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

11-06-1996 11:07:48

A. PANGAN-MCELROY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, FREDERICK J. KING, in a field survey on May 31, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-N and rows 2-13, containing numerical values for section identification.

A. Description of original monument and accessories and/or subsequent restoration:

H-13 - SOUTH 1/4 CORNER SECTION 34

Dec. 1839 - Original Post set by Clason, Dep. Sur. N48°E - 19 lks (12.54') - 24" B. Oak
N39°W - 57 lks (37.62') - 20" B. Oak
Aug. 1971 - Act 74 (L1, P6) by K. Ostling #10068 N50°E - 9.7' - 6" R. Oak
N14°W - 8.6' - 7" R. Oak

Cor H-1 Aug. 1971 - Act 74 (L1, P3) by K. Ostling #10068
T28N-R2E Set DNR Pipe & Cap by Sngl Prop.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 - SOUTH 1/4 CORNER OF SECTION 34

Found Rec DNR Pipe & Cap (L1, P6) K. Ostling
N14°W - 8.6' - Fnd Blz in Rec Oak
N50°E - 9.7' - Fnd Blz in Rec Oak
West - 32.34' - Fnd Rec DNR Pipe & Cap @ Corner H-1 (28-2)

No Original Government Corner Evidence Found

This Corner approved by County Peer Review on June 7, 1996, as the best available evidence of the re-establishment of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 - SOUTH 1/4 CORNER SECTION 34

1" Rec DNR Pipe & Cap - 4" Aluminum
N50°E - 10.27' - Set S&T SE side of 10" Oak
East - 34.35' - Set S&T N side Fnc Corner Post
S25°W - 24.72' - Set S&T E side of 20" Oak
N14°W - 8.59' - Set S&T W side of 12" Oak
West - 32.14' - Corner H-1 (28-2)



APPROVED BY PEER GROUP

Signed by Frederick J. King Date October 25, 1996

Surveyor's Michigan License No. 25852 JUN 07 96

Handwritten initials R and L.H.B.