

MAY 1 6 1997

COMMISSION

Montmorency County Remonumentation

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Liber 00012 Page 0238

For corners in

MONTMORENCY
(County)

Located In: ALBERT TWP. Corner Code #

- 1. Public Land Survey T 29N R 2E K-13
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

11-06-1996 11:08:29

A. PANGAN-MCELROY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
- 5. Private Claims

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

I, FREDERICK J. KING, in a field survey on June 3, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-13 - CORNER COMMON TO SECTIONS 35 & 36 (Cor K-1 (28-2) Intersected 42 lks (27.72') W of K-13
 Dec. 1839 - Original Post set by Clason, D.S. N16°E - 26 lks (17.16') 10" Tam
 N31°W - 19 lks (12.54') 14" Tam
 Aug. 1971 - Act 74 9L1, P 7) by K. Ostling #10068
 This Cor fnd by E. Houghton in mid 30's (Iron Bolt) Remarkd by M. Schaaf with pipe in conc. We fnd both pipe & bolt and replaced with DNR Pipe & Cap
 S56°E - 11.3' - 8" Cedar N52°W - 13.0' - 16" Cedar ***Original BT***
 N88°E - 23.9' - 7" Cedar Corner K-1 (28-2) is 27.7' West
 Cor K-1 Aug. 1971 - Act 74 (L1, P 4) by K. Ostling #10068 This Cor was found by E. Houghton
 T28N-R2E in Mid 30's, previously established by unknown. Remarkd by M. Schaaf.
 Set DNR Pipe & Cap Corner K-13 (29-2) is 27.7' EAST

B. Description fo corner evidence found and/or method applied in restoring or reestablishing corner

K-13 - CORNER COMMON TO SECTIONS 35 & 36
 Found Rec. DNR Pipe & Cap (L1, P 7) K. Ostling
 S56°E - 11.3' - Found blaze in Rec Cedar (L1, P 7)
 N52°W - 13.0' - Found blaze in Rec Cedar (L1, P 7) ***Original BT***
 N88°E - 23.9' - Found blaze in Rec Cedar (L1, P 7)
 West - 27.7' - Found Rec DNR Pipe & Cap @ Corner K-1 (28-2)

This Corner Approved by County Peer Review on June 7, 1996, as a perpetuation of the Original Government Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 - CORNER COMMON TO SECTIONS 35 & 36
 1" Rec DNR Pipe & Cap - 4" Aluminum
 N88°E - 24.14' - Set S&T S side of 12" Cedar
 S56°E - 10.72' - Set S&T SW side of 15" Cedar
 S70°W - 10.85' - Set S&T N side of 12" Tam
 N52°W - 13.08' - Set S&T NE side 24" Cedar
 West 27.75' - Corner K-1 (28-2)



Signed by Frederick J. King APPROVED BY PEER GROUP Date October 26, 1996
 Surveyor's Michigan License No. 25852

JUN 07 96

L.H.B.