

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 29 N. R. 3 E.	G-10; H-11; I-11
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER \_\_\_\_\_

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 14, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- G-10 Set corner from probable U.S.B.T. stump NW. Falls within 2' of midpoint on line between section corners.
- H-11 Set corner from NW U.S.B.T. stump, in place, with good face. Falls in road cut, no previous monument found.
- I-11 Found RR iron at road intersection E-W-S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-10	H-11	I-11
Set DNR monument & cedar post	Set DNR monument & cedar post	Left RR iron in place
5" Maple N34°E 66.2	5" Maple N18°W 55.95	9" Maple N02°W 57.65
4" R. Pine S67°E 34.5	8" Maple N26°E 30.7	Nail in 10" Spruce
3" R. Pine S02°W 9.2	Corner is 4' North of $\frac{1}{4}$ of gravel road	N47°W 55.5

SIGNED BY *Kenneth J. Ostling* DATE 12

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ LOUD TOWNSHIP  
 MONTMORENCY COUNTY