

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Montmorency Located In \_\_\_\_\_  
(County)

1. Public Land Survey \_\_\_\_\_

2. Property Controlling in Section  
 S 30 T 29N R 3E 1  
 S 30 T 29N R 3E 8

3. Miscellaneous Property in Section  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

Register of Deeds Stamp & File Number

I, Carl T. Kiiskila, in a field survey on September 24, 2010 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9	●											
10	●	30		29		28		27		26		25
11												
12	31		32		33		34		35		36	
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1- W1/16 Cor. common to sections 19 & 30. 8- CW1/16 cor. Section 30.
- This corner was not set during the original Government Survey. This corner was not set during the original Government Survey.

**B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:**

- 1- W1/16 Cor. Common to sections 19 & 30. 8- CW1/16 Cor. Section 30.
- Set a 1" x 48" Galv. Pipe with P.S. cap #33981 in Hunt Creek per Standard BLM Procedure. Set 2" dia. Aluminum cap on 5/8" x 34" rebar per Standard BLM Procedure.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- 1- W1/16 cor. Common to sections 19 & 30. 8- CW1/16 corner section 30.
- Set a 1" x 48" galv. Pipe with P.S. cap #33981. Stamped 2" dia. Aluminum cap on a 5/8" x 34" rebar
- Wits: N60°E 39.30' set N&T SE side 7" Tamarack  
 S66°E 24.10' to set N&T S side 11" Balsam Fir  
 N89°E 14.05' to set N&T S side 4" Spruce  
 East bank of Hunt Creek East 2'  
 Corner falls 4' South of old E-W road bed  
 Set Blue Carsonite Post East 12'
- Wits: N25°E 40.13' to set N&T W side 8" R. Maple  
 S 34°E 51.05' to set N&T SW side 10" W. Pine  
 S59°W 62.40' to set N&T N side 20" R. Oak  
 N21°W 38.65' to set N&T W side 12" S. Maple  
 Corner falls 15' South of E-W gravel road and 11' East of Drive South  
 Set Blue Carsonite Post 34' North

Carl T. Kiiskila

Surveyor's Michigan License No.: 33981



12-20-10