

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED  
MONTMORENCY CITY  
REGISTER OF DEEDS  
DEC 20 10 12 AM '93  
A. PANJAN-MCELROY

For corners in

Montmorency (County)	Located In:	Corner Code =#
1. Public Land Survey	T <u>29N</u> R <u>3E</u>	<u>A-6</u> ✓
	T <u>29N</u> R <u>3E</u>	<u>A-7</u>
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

APPROVED BY  
PEER GROUP

NOV 0 5 93

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Donald E. Marlatt, in a field survey on December 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- |   |   |
|---|---|
| (A-6) W. 1/4 Cor. Sec. 18, T29N, R3E<br>Post set by Lewis Clason 1839.<br>Spruce Pine 6-N 52 W-9<br>Spruce Pine 6-S 48 E-21<br>M.S.H.D. Project 60-10 Field Notes 1956.<br>Called for 4" x 4" Cedar (No witnesses). | (A-7) S.W. Cor. Sec. 18, T29N, R3E<br>Post set by Lewis Clason 1839.<br>Spruce Pine 8-S 39 W-30<br>Y. Pine 24-N 29 W-99<br>Spruce Pine 8-S 39 E-32<br>Y. Pine 24-N 62 E-61<br>M.S.H.D. Project 60-10 Field Notes 1956.<br>Act 74 by D.E. Porter L. 1, P. 8. |
| (A-7) D.E. Porter for Shell Western E. & P. February 1993.  |   |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- |  |   |
|--|---|
| (A-6) W. 1/4 Cor. Sec. 18, T29N, R3E<br>Fnd. 4" x 4" Cedar & 3" pipe.<br>S 64° E 10" Cedar 6.03'<br>S 60° W 12" Cedar 10.92'<br>N 37° W 13" Cedar 31.30' | (A-7) S.W. Cor. Sec. 18, T29N, R3E<br>Fnd. Boat Spike.<br>Oak 17" N 61° E 49.22'<br>Oak 6" S 30° E 47.40'<br>J. Pine S 25° W 53.82' |
|--|---|

No evidence of original corner. No evidence of original corner.

The Peer Group approved (A-6) as the best available evidence of the position of the original corner.  
The Peer Group approved (A-7) as the best available evidence of the re-establishment of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |   |   |
|---|---|
| (A-6) W. 1/4 Cor. Sec. 18, T29N, R3E<br>Set conc. Mon. & Re-Mon cap.<br>N 42° E 22" W. Pine 33.53'<br>S 64° E 10" Cedar 6.03'<br>S 60° W 12" Cedar 10.92'<br>N 37° W 13" Cedar 31.30' | (A-7) S.W. Cor. Sec. 18, T29N, R3E<br>Set conc. Mon. & Re-Mon cap.<br>N 65° E 24" Oak 49.15' Ex.<br>S 30° E 15" Oak 48.43'<br>S 35° W 16" N. Pine 58.07'<br>N 12° W 5" Maple 50.93' |
|---|---|

Note: Witnesses marked with 30 penny spikes & I.D. tags #18660.

Signed by Donald E. Marlatt Date Dec 15, 1993

Surveyor's Michigan License No. 18660

