

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
MONTMORENCY CITY
REGISTER OF DEEDS
DEC 20 10 12 AM '93
A. PANDAN-ROELROY

For corners in Montmorency (County) Located In: Corner Code #
1. Public Land Survey T 29N R 3E A-8
T 29N R 3E A-9
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

APPROVED BY PEER GROUP

NOV 05 93

Register of Deeds Stamp & File Number

Lot No. Recorded Plat
Private Claims

Grid table with columns A-M and rows 2-13. Contains numbers 1-36.

Donald E. Marlatt, in a field survey on December 10, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

- (-8) W. 1/4 Cor. Sec. 19, T29N, R3E Post set by Lewis Clason 1839. W. Pine 10-S 59 W-16 W. Pine 10-N 24 W-42 M.S.H.D. Project 60-10 field notes 1956 Act 74 by D.E. Porter L. 1, P. 492 Survey by D.E. Marlatt L. 2, P. 121 Survey by Fred King L. 3, P. 520 Survey by D.E. Porter for Shell Western E. & P. Feb. 1993.
(A-9) S.W. Cor. Sec. 19, T29N, R3E Post set by Lewis Clason 1839. Y. Pine 22-S 54 W-1.76 Beech 10-S 65 E-39 Hemlock 28-N 68 W-33 M.S.H.D. Proj. 60-10 field notes 1956 Act 74 D.E. Porter L. 1, P. 8 Survey by Fred King L. 3, P. 520 Survey by D.E. Marlatt Dated 10-13-1981 Survey by D.E. Porter for Shell Western E. & P. 1993.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (-8) W. 1/4 Cor. Sec. 19, T29N, R3E Fnd. 1/2" rod. S 10° E 5.60' 12" Oak N 80° W 20.07' 8" Oak N 15° E 14.89' 12" Oak N 1° E 35.85' 16" Oak
(A-9) S.W. Cor. Sec. 19, T29N, R3E Fnd. 1/2" rod by DE La Mater 1932. 22" Oak N 54° W 35.32' 8" Oak S 14° E 20.38' 9" Oak N 83° E 20.0'

No evidence of original corner. No evidence of original corner.

The Peer Group approved (A-8) & (A-9) as the best available evidence of the position of the original corner.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (-8) W. 1/4 Cor. Sec. 19, T29N, R3E Placed Re-Mon. cap on 1/2" rod. S 17° E 5.60' 12" Oak N 70° W 19.93' 10" Oak N 35° E 14.89' 12" Oak N 8° E 35.88' 16" Oak
(A-9) S.W. Cor. Sec. 19, T29N, R3E Placed Re-Mon. cap on 1/2" rod. N 55° W 24" Oak 33.98' S 50° W 14" Oak 35.52' S 9° E 14" Oak 20.33' N 87° E 12" Oak 30.00'

Witnesses marked with 30 penny spikes & I.D. tags #18660.

Signed by Donald E Marlatt

Date Dec 15, 1993

Surveyor's Michigan License No. 18660

