

Montmorency County Remonumentation

Libet 12 Page 12

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

08104  
A. PANGAN-MCELROY  
RECEIVED  
MONTMORENCY CITY  
REGISTRY OF DEEDS  
DEC 20 10 12 AM '93

For corners in  
Montmorency  
(County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey T 29N R 3E A-10  
T 29N R 3E A-11 ✓  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

NOV 05 93

APPROVED BY  
PEER GROUP

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Donald E. Marlatt, in a field survey on December 10, 19 93,  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 10) W. ¼ Cor. Sec. 30, T29N, R3E (A-11) S.W. Cor. Sec. 30, T29N, R3E  
Post set by Lewis Clason 1839. Post set by Lewis Clason 1839.  
Tamarack 9-S 52 W-31, Cedar 12-N 28 W-36 Hd. Maple 10-S 73 W-35  
M.S.H.D. Proj. 60-10 field notes 1956. W. Pine 20-N 41 W-14  
Act 74 by Ken Ostling L. 1, P. 187. W. Pine 36-N 55 E-19  
Survey by Ken Ostling 1975. Hd. Maple 8-S 34 E-23  
Survey by R.S. Scott Assoc. Inc. L. 2, P. 450. M.S.H.D. Proj. 60-10 field notes 1956.  
Survey by D.E. Marlatt 10-13-1981. Act 74 by Ken Ostling L. 1, P. 187.  
Survey by D.E. Marlatt 7-2-1989. Survey by Ken Ostling 1975.  
Survey by D.E. Porter 1993. Act 74 by Norm Quaine L. 1, P.479 &  
L. 1, P. 501.  
Survey by D.E. Porter for Shell Western E. & P. 1993.

Description of corner evidence found and/or method applied in restoring or reestablishing  
corner:

- 10) W. ¼ Cor. Sec. 30, T29N, R3E (A-11) S.W. Cor. Sec. 30, T29N, R3E  
Fnd. Conc. Mon. Fnd. Conc. Mon.  
S 80° W 9" Spruce 77.0' N 60° W 35.11' 6" Oak  
N 50° E 9" Balsam 23.0' S 59° W 69.60' P. Pole  
N 43° E 69.65' 18" Cedar  
S 51° E 43.60' 14" Basswood  
No evidence of original corner. No evidence of original corner

The Peer Group approved (A-10) as a perpetuation of the original government corner.  
The Peer Group approved (A-11) as the best available evidence of the reestablishment of orig.  
Description of monument for corner and accessories established to perpetuate locating the position of the corner.

- 10) W. ¼ Cor. Sec. 30, T29N, R3E (A-11) S.W. Cor. Sec. 30, T29N, R3E  
Placed Re-Mon. cap on Conc. Mon. Placed Re-Mon. cap on Conc. Mon.  
S 1° E 4" Spruce 13.4' N 43° E 18" Cedar 69.63'  
S 65° W 12" Balsam 43.87' S 52° E 12" Basswood 43.65'  
N 53° E 9" Balsam 23.08' S 60° W P. Pole 69.60'  
N 18° W 11" Poplar 27.51' N 60° W 6" Oak 35.08'

Witnesses marked with 30 penny spikes & I.D. tags #18660.

Surveyed by Donald E. Marlatt Date Dec 15, 1993

Surveyor's Michigan License No. 18660

