

Montmorency County Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Montmorency  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 29N R 3E A-12 ✓  
T 29N R 3E A-13  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

**APPROVED BY  
PEER GROUP**

NOV 0 5 93

08145

A. PANGOR-MCELROY

RECEIVED  
MONTMORENCY CITY  
REGISTER OF DEEDS  
DEC 20 10 12 AM '93

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Donald E. Marlatt, in a field survey on December 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (-12) W. ¼ Cor. Sec. 31, T29N, R3E (A-13) S.W. Cor. Sec. 31, T29N, R3E  
Post set by Lewis Clason 1839. Post set by Lewis Clason 1839.  
Hemlock 9-S 39 W-46 Hemlock 20-N 46 W-59  
Beech 15-N 74 W-32 Hemlock 24-S 69 E-37  
M.S.H.D. Proj. 60-10 field notes 1956. M.S.H.D. Proj. 60-60 field notes 1956.  
Act 74 by Norm Quaine L. 1, P. 478 Act 74 by Norm Quaine L. 1, P. 478  
Survey by D.E. Porter for Shell Western Survey by D.E. Porter for Shell  
E. & P. 1993. Western E. & P. 1993.  
Act 74 by Ken Ostling L. 1, P. 186.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (-12) W. ¼ Cor. Sec. 31, T29N, R3E (A-13) S.W. Cor. Sec. 31, T29N, R3E  
Fnd. Conc. Mon. Fnd. 1" x 3' pipe & T on bottom.  
S 63° W 29.65' 20" Tw. Maple N 68 W 59.18' 10" J. Pine NBT  
S 89° W 35.0' N.E. Cor. Power box S 74 W 72.69' 18" R. Pine NBT  
N 58° W 25.25' 20" Maple N 50° E 63.8' 4" Oak  
S 33° E 65.71' 16" Maple N 78° E 41.22' 12" Tw. Aspen  
No evidence of original corner. No evidence of original corner.  
The Peer Group approved (A-12) as the best available evidence of the reestablishment of the original corner.  
The Peer Group approved (A-13) as a perpetuation of the original government corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (-12) W. ¼ Cor. Sec. 31, T29N, R3E (A-13) S.W. Cor. Sec. 31, T29N, R3E  
Placed Re-Mon. cap on Conc. Mon. Placed Re-Mon. cap on 1" pipe.  
N 46° E 6" Maple 58.67' S 74° W 18" N. Pine 72.69'  
S 34° E 15" Maple 65.83' N 68° W 10" J. Pine 59.18'  
S 62° W Tw. 11" & 15" Maple 29.65' N 50° E 4" Oak 63.80'  
N 44° W Tw. 11" & 16" Maple 25.26' N 78° E 12" Tw. Aspen 41.20'

Witnesses marked with 30 penny spikes & I.D. tags #18660.

Signed by Donald E. Marlatt

Date Dec 15, 1993

Surveyor's Michigan License No. 18660

