

DEC 18 1995

Montmorency County Remonumentation

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Libert 00012 Page 0171

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Montmorency (County)	Located In:	Corner Code =#
	LOUD TWP.	
1. Public Land Survey	T 29N R 3E	E-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
MONTMORENCY COUNTY  
Recorded & Filed  
  
11-21-1995 13:20:58  
  
A. PANGAN-MCELROY  
Register of Deeds  
18666

I, Donald E. Marlatt, in a field survey on 3-31, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(E-1) N.W. corner Section 4, T 29 N, R 3 E.  
Post set by Lewis Clason in 1839.  
S 42\* E 18" Hemlock 22 links  
S 83\* W 22" Hemlock 22 links  
DNR L.C.R. on 8-1-1960. FOUND WOOD POST  
Act 74 by Ted Miller on 7-25-1972, Recorded L. 1, P. 1. FOUND WOOD POST & 3/4" PIPE  
Act 74 DNR, Ken Ostling on 12-5-1974, Recorded L. 1, P. 117. FOUND WOOD POST-SET DNR MON.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E-1) N.W. corner of Section 4, T 29 N, R 3 E.  
Found DNR monument.  
N 12\* E 15" Ash Tag #10698 (Ted Miller)  
DNR monument 9.89' West South corner common to Sections 32 & 33, T 30 N, R 3 E.  
No evidence of original corner.


**APPROVED BY  
PEER GROUP**

JUN 0 2 95

*D.E.B.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E-1) N.W. corner of Section 4, T 29 N, R 3 E.  
Left DNR monument in place.  
N 12\* E 15" Ash 27.59'  
S 20\* W 10" Basswood 6.53'  
S 50\* E 12" Basswood 11.78'  
N 74\* E 9" Oak 12.26'  
Witnesses marked with a 30" penny spike & P.S. tag #18660.  
Approved by the Peer Group on June 2, 1995 as the best available evidence of the position of the original corner.



Signed by Donald E. Marlatt Date 11-7-95  
Surveyor's Michigan License No. 18660