

Montmorency County Remonumentation

Liber 00012 Page 0172

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MONTMORENCY</u> <small>(County)</small>	Located In: LOUD TWP.	Corner Code # G-1
1. Public Land Survey	T <u>29N</u> R <u>3E</u>	<u>G-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
MONTMORENCY COUNTY  
Recorded & Filed  
11-21-1995 13:21:07  
A. PANGAN-MCELROY  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, DONALD E MARLATT, in a field survey on 4-2, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

G-1 NORTH CORNER COMMON TO SEC'S 3 & 4, T29N, R3E.  
POST SET BY LEWIS CLASON 1839. W. PINE 10"-S60°W-38 L., CEDAR 8"-S66°E-19 L.  
FRANK SMITH NOTFS 1940, NO COR. DESCRIPTION-10"CEDAR S64°30'E 12.54'-14"BAL. S26°30'E 32.15'-14"CEDAR S16°W 39.25'- 5"W.PINE N26W 35.20'.  
SURVEY BY N.C.CALDWELL 1-5-68-FOUND PIPE, PLACED 1/2"ROD & CAP, S16°W 39.25' 16"CFDAR, N26°W 35.2' 8"W.PINE.  
ACT 74 BY T. MILLER L. 1, P. 2.  
SURVEY BY T. MILLER L. 2, P. 108, NO WIT. OR CORNER DESCRIPTION.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-1 NORTH CORNER COMMON TO SEC'S 3 & 4, T29N, R3E.  
FOUND 1/2"ROD IN 1 1/4" PIPE WITH GRADER BLADE  
N43 1/2°E 10"CEDAR 28.1'  
N45 1/2°W 18"W.PINE 31.9'

SURVEY &  
REMONUMENTATION

DEC 18 1995

COMMISSION

NO EVIDENCE OF ORIGINAL CORNER



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1 NORTH CORNER COMMON TO SEC'S 3 & 4, T29N, R3E.  
SET CONC. MONUMENT & REMON. CAP#18660  
S48°E 15"CFDAR 26.8'  
S 2°E 12"CEDAR 16.45'  
N23°W 15"CEDAR 20.57'  
N20°E 10"CFDAR 28.58'  
WITNESSES MARKED WITH 30 PENNY SPIKES & TAG #18660  
APPROVED BY PEER GROUP ON JUNE 2, 1995 AS A PERPETUATION OF THE ORIGINAL GOV'T. CORNER.

APPROVED BY  
PEER GROUP

JUN 02 95

*[Signature]*

Signed by Donald E Marlatt

Date 11-17-1995

Surveyor's Michigan License No. 18660