

Montmorency County Remonumentation

Liber 00012 Page 0175

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Montmorency <small>(County)</small>	Located In:	Corner Code #
	LOUD TWP.	
1. Public Land Survey	T 29N R 3E	I-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
MONTMORENCY COUNTY  
Recorded & Filed

11-21-1995 13:21:33

A. PANGAN-MCELROY  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Donald E. Marlatt, in a field survey on 4-24- 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- (I-1) N.W. corner of Section 2, T 29 N, R 3 E.  
Post set by Lewis Clason in 1839.  
S 30\* E 8" W. Birch 26 links  
S 72\* W 10" Aspen 22 links

**SURVEY &  
REMONUMENTATION**

DEC 18 1995

COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (I-1) No evidence of original corner. (Fence line to the South lines up with the South corner Sections 34 & 35, T 30 N, R 3 E).  
Set concrete monument & remonumentation cap on the South line of Section 35, T 30 N, R 3 E, 6.62' (Pro-rated).  
East of S.W. corner Section 35, T 30 N, R 3 E.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (I-1) N.W. corner of Section 2, T 29 N, R 3 E.  
Set concrete monument & remonumentation cap. #18660  
S 52\* E 6" Balsam 39.41'  
S 01\* E 5" Balsam 22.90'  
S 20\* W 4" Balsam 30.52'  
S 50\* W 7" Balsam 35.41'

**APPROVED BY  
PEER GROUP**

JUN 02 95

*JLB*

Witnesses marked with a 30" penny spike & P.S. tag #18660.  
Approved by the Peer Group on June 2, 1995 as a careful and faithful establishment of the position of the corner.

Signed by Donald E. Marlatt

Date 11-7-1995

Surveyor's Michigan License No. 18660