

APR 24 1995

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Montmorency  
(County)

Located In: Loud Twp. Corner Code #

- 1. Public Land Survey T 29N R 3E (K-13)
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

APPROVED BY  
PEER GROUP

AUG 05 94

STATE OF MICHIGAN  
MONTMORENCY COUNTY  
Recorded & Filed

11-02-1994 15:41:50

A. PANGAN-MCELROY,  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Larry G. Beauregard, in a field survey on May, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (K-13) GLO post set by Lewis Clason December 12, 1839.  
Wits: Beech 24" N 27° E 15 links Beech 11" N 72° W 40 links  
Marcus Schaaf P.S. #3104 set or found 1/2" bar no date. Wits marked: (N 40° W 25.3' 14" Y. Pine), (S 11° E 26.1' 26" W. Pine stump) and (N 89° W 28.3' 5" Black Oak).  
Norman C. Caldwell P.S. #12018 in 1966 set R.R. spike for closing corner for Secs. 1 & 2, T 28 N, R 3 E, but lat used as standard corner on Co. line, see letter in file. Wits: (48.0' Tel. Pole N 45° E) (18" Elm N 80° E 61.9')  
Delmer E. Porter P.S. #15410 in 1973 found 1/2" rod in monument box 5.5' west of M-33 C/L. No witnesses marked.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (K-13) Found existing 1/2" bar in monument box 5.5' west of M-33 C/L. Placed 3" diam., Aluminum cap #18654 marked Montmorency County Remonumentation corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (K-13) Section corner common to Secs. 35 and Sec. 36, T 29 N, R 3 E.  
Existing 1/2" bar in monument box with Re-mon. cap on same, P.S. #18654. Accepted as a careful and faithful establishment of the position of the corner. Approved by the Peer Group on August 5, 1994.

P. Pole N 50° W 57.88' Ex. MDOT tag  
P. Pole S 30° W 126.77'

P. Pole N 80° E 150.85'  
4" Square treated post in concrete (Mont. Co. Rd. s:  
N 45° E 56.61'.

Placed P.K. nail & P.S. tag #18654 (typ)

Signed by Larry G. Beauregard

Date 11/2/94

Surveyor's Michigan License No. 18654