

**Montmorency County Remonumentation**

Liber **00012** Page **0178**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MONTMORENCY</u> (County)	Located In: <b>LOUD TWP.</b>	Corner Code <b>##</b> <b>L-1</b>
1. Public Land Survey	T <u>29N</u> R <u>3E</u>	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
MONTMORENCY COUNTY  
Recorded & Filed

11-21-1995 13:22:10

A. PANGAN-MCELROY  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, DONALD E MARLATT, in a field survey on 4-24, 19 95,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(L-1) NO COR. SET IN ORIGINAL SURVEY.  
MSHD WIT. BY N.C. CALDWELL 1-7-1965 FOUND 4'X 4' POST & SET 3/4" PIPE.  
N 6°E 75.16' 7"BALSAM -S73°E 28.26' 4"BALSAM-S30°E 22.09' 11"BALSAM(NBT)  
ACT 74 BY L. BEAUREGARD, RECORDED IN L. 1, PAGE 120.  
R.S. SCOTT ENG. SURVEY ON 1-7-1975, L. 2, P. 37.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-1 NORTH 1/4 COR. SEC. 1, T29N, R3E.  
FOUND CONC. MONUMENT & CAP#18654 & sq. cedar stake  
S70°W 12"SPRUCE 29.21'  
S68°E 14"SPRUCE 28.4'

SURVEY &  
REMONUMENTATION

**APPROVED BY  
PEER GROUP**

DEC 18 1995

JUN 02 95

NO EVIDENCE OF ORIGINAL CORNER.

COMMISSION

*LEB*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1 NORTH 1/4 COR. OF SEC. 1, T29N, R3E  
PLACED REMON. CAP ON CONC. MONUMENT#18660.  
S70°W 12"SPRUCE 29.21' EXISTING  
N48°E 12"SPRUCE 58.59'  
S85°E 16"SPRUCE 55.73'  
S68°E 14"SPRUCE 28.4' EXISTING



WITNESSES MARKED WITH 30 PENNY SPIKES & P.S. TAG #18660  
APPROVED BY PEER GROUP ON JUNE 2, 1995 AS THE BEST AVAILABLE EVIDENCE OF  
THE POSITION OF THE ORIGINAL CORNER.

Signed by Donald E Marlatt

Date 11-7-1995

Surveyor's Michigan License No. 18660