

Montmorency County Re-monumentation

08233

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
MONTMORENCY CITY
REGISTER OF DEEDS
DEC 23 3 01 PM '93

Liber 12 Page 35

For corners in

Table with columns: MONTMORENCY (County), Located In: RUST TWP., Corner Code #, and numbered rows 1-5 for Public Land Survey, Property Controlling, Miscellaneous, Lot No., and Private Claims.

Register of Deeds Stamp & File Number

Grid table with columns A-L and rows 2-13, containing numbers 1-36.

I, Frederick J. King, in a field survey on August 9 September, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-7 SW Cor., Sec. 18 & NW Cor., Sec. 19, T.29 N., R.4 E. A-8 West 1/4 Cor., Sec. 19, T.29 N., R.4 E.
Orig. Post by Lewis & Clason - Nov. 1839
N50W-148 lks(97.68')Pine, S80W-27 lks(17.82')Pine
1946-Unrec Sur by F. Smith - Does not indicate Corner Evidence of Wit.
1972-Act 132 Sur by N. Caldwell, Rec L. 1, Pg. 211
Fnd. Conc. Mon. by Smith, S35E-19.6'-6" Maple
S25W-45.5'-6" Oak(NBT) N15E-51.5'-10" Oak(NBT)
ACT 74 by N. Caldwell, Rec. Bk 1, Pg 31 - Feb 1972
Fnd. Conc. Mon. - Same Wit. as Sur. L.1, Pg. 211

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7 SW Cor., Sec. 18 & NW Cor., Sec. 19, T.29 N., R.4 E. A-8 West 1/4 Cor., Sec. 19, T.29 N., R.4 E.
Fnd. Rec. Conc. Mon. (Bk. 1, Pg. 31)
S.35°E. - 19.6' - 6" Maple (Rec)
NO ORIGINAL CORNER EVIDENCE FOUND

Approved by Montmorency County Peer Review on Sept. 24, 1993, as the best available evidence of the original corner.

Approved by Montmorency County Peer Review on Sept. 24, 1993, as a careful and faithful re-establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-77 SW Cor., Sec. 18 & NW Cor., Sec. 19, T.29 N., R.4 E. A-8 West 1/4 Cor., Sec. 19, T.29 N., R.4 E.
Set Mont. Co. Re-Mon Cap on Fnd. Conc. Mon.
N.70°E. - 16.96' - Set Tag SE Sd. 10" Maple
S.35°E. - 19.88' - Set Tag NE Sd. 10" Maple
S.30°W. - 26.22' - Set Tag W. Sd. 12" Maple
N.55°W. - 11.95' - Set Tag S. Sd. 12" Maple
S.45°E. - 1.8' - Cedar R.T. Post being used as Fnc Corner

NOTE: All Witnesses Marked with Db1. Headed Nails & I.D. Tags#25852

Signed by Frederick J. King

Date Dec. 23, 1993

Surveyor's Michigan License No. 25852

