

Montmorency County Remonumentation

08224

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MONTMORENCY (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>29N</u> R <u>4E</u>	<u>A-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED
MONTMORENCY COUNTY
REGISTER OF DEEDS
DEC 23 3 01 PM '93
A. PINSKY-WELTON

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Frederick J. King, in a field survey on September, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-9 SW Cor. Sec. 19 & NW Cor. Sec. 30, T.29 N., R.4 E.
 Orig. Post by Lewis Clason - Nov. 1839 - S54W - 1.76 lks (1.16') No other Tree convenient
 1946 - Un-Rec Sur by F. Smith - Doesn't Indicate Corner Evidence or Wit.
 1971 - Un-Rec Sur by N. Caldwell - Fnd Rec Bed Rail - N58W-29.3'-7" Oak(R), S48E-44.8'-7" Oak(R), N49E-28.5'-8" Oak(R)
 1972 - Act 132 Sur by N. Caldwell - Fnd Rec Bed Rail - Set Conc. Mon. - Same Wit. as 1971 Caldwell Sur.
 Act 74 by N. Caldwell Rec. Bk. 1, Pg. 31 - Feb. 1972 - Fnd. Rec Bed Rail - Set Conc. Mon. - Same Wit. as 1972 Act 132 Rec L.1, Pg. 211.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-9 SW Cor., Sec. 19 & NW Cor. Sec. 30, T.29 N., R.4 E.
 Fnd. Rec. Conc. Mon. (Bk. 1, Pg. 31)
 Fnd. Rec. Bed Rail - S.30°E. - 0.3' of Conc. Mon.
 No Caldwell Wit. Found
 NO ORIGINAL CORNER EVIDENCE FOUND

Approved by Montmorency County Peer Review on Sept. 24, 1993, as the best available evidence of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-9 SW Cor., Sec. 19 & NW Cor. Sec. 30, T.29 N., R.4 E.
 Set Mont. Co. Re-Mon Cap on Fnd Conc. Mon.
 N.20°E. - 27.29' - Set Tag W. Sd. 20" Maple
 S.80°E. - 46.33' - Set Tag S. Sd. 10" Twin Maple
 S.35°E. - 4.00' - Set Tag NE Sd. 10" Maple
 N.80°W. - 40.83' - Set Tag S. Sd. 10" Maple
 Corner is ±150' N off E-W 2 Track Trail
 Fnd Cedar R.T. Post Along Side Corner

NOTE: All Witnesses are Marked with DBL. Headed Nails & I.D. Tag #25852



Signed by Frederick J. King

Date Dec. 23, 1993

Surveyor's Michigan License No. 25852