

Montmorency County Remonumentation

MAY 1 9 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 00012 Page 0192

For corners in

Montmorency (County)	Located In: Rust Township	Corner Code #
1. Public Land Survey	T 29N R 4E	F-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
MONTMORENCY COUNTY  
Recorded & Filed

09-27-1996 13:25:01

A. FANGAN-MCELROY  
REGISTER OF DEEDS

~~Liber 00001 Page 0532~~  
Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Larry G. Beauregard, in a field survey on June, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
F-13 South 1/4 corner Section 33.

Nov. 1839 - Original post set by Lewis Clason D.S. Wit's marked: (N 40° E 48 links 26" Y. Pine) (N 36° W 36 links 24" Y. Pine).

1913 - C.O. Seeley Oscoda Co. Surveyor found stake. US B.T. gone. No Wit's. marked.

1956 - Gordon G. Slattery PE # 3694 set conc. mon. wit's marked: (N 45° E 23.4' 10" R. Oak)(N 35° W 21.4' 10" R. Oak)

1981 - Norman C. Caldwell PS # 12018 found conc. mon. by Slattery in E & W fence line. Wit's marked: (N 45° W 1.0' DNR post) (N 45° E 23.4' 10" R. Oak (R)) (South 24.0' Road E & W) (N 40° E 31.7' Remains of original B.T.) (N 36° W 23.8' Remains of original B.T.).  
Filed Act # 132, Rec. L. 3, P. 266, Oscoda Co. Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found conc. mon. in good condition with DNR post along side.

Placed Re-mon cap # 18654 on same.

7.34' feet West Oscoda Co. std. corner. N 1/4 corner Section 4, T 28N, R 4E.

**APPROVED BY  
PEER GROUP**

JUN 07 96  
L.G.B.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13 South 1/4 corner Section 33

4" dia. x 36" conc. mon. & re-mon cap. Accepted as a perpetuation of the original government corner.  
Approved by the Peer Group on June 7, 1996.

- N 40° E 11.32' Tw. 16" Oaks
- N 65° W 79.83' 10" Oak
- S 65° W 87.97' 7" Maple in clump
- S 35° W 73.75' Tw. 17" Oaks

Placed 60d penny spike, P.S. tag # 18654 & blaze. (typ)



Signed by Larry G. Beauregard Date 9-24-96  
Surveyor's Michigan License No. 18654