

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MONTMORENCY
(County)

Located In:

Corner Code #

VIENNA TWP.

- 1. Public Land Survey T 30N R 1E
T 30N R 1E
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

A-1 _____
A-2 _____

RECEIVED
 MONTMORENCY CITY
 REGISTER OF DEEDS
 DEC 23 2 59 PM '93
 A. PANGAN-HELROY

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Frederick J. King, in a field survey on August - September, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-1 Northwest Cor. Sec. 6, T.30 N., R.1 E.
 Orig. Post by John Hodges, D.S. - May 1839
 S.62°W-21 lks(13.86')Pine N.24°W-111. lks(73.26') Aspen
 S.56°E-26 lks(17.16')Asp. N.60°E-30 lks (19.80') Aspen
 1974 - Act 132 Sur. by F. King, Rec. L.3, Pg.269-270
 Fnd. Conc. Mon. in E-W Enc. - No Witnesses
 1988 - Un-Rec. Sur. by D. Porter - Fnd. Mon. - No Wit.
 1989 - Act 132 Sur. by F. King, Rec. L.3, Pg.494-495
 Fnd. Conc. Mon. - No Witnesses
 NO ACT 74 RECORDED FOR THIS CORNER

A-2 West 1/4 Cor. Sec. 6, T.30 N., R.1 E.
 Orig. Post by John Hodges, D.S. - May 1839
 S.31°W. - 22 lks (14.52') Sugar
 N.47°W. - 23 lks (15.18') Sugar
 1974 - Act 132 Sur. by F. King, Rec. L. 3, Pg. 269-270
 Set 1/2" Iron by Sngl Prop. 2697.98' N-of A-3
 (GN=2640')-2213.01' S of A-1 (GN=2165.77')
 1988 - Un-Rec. Sur. by D. Porter - Fnd. & Accept Iron
 by King - No Witnesses
 1989 - Act 132 Sur. by F. King, Rec. L.3, Pg. 494-495
 Fnd. Rec. Iron - No Witnesses
 NO ACT 74 RECORDED FOR THIS CORNER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-1 Northwest Cor. Sec. 6, T.30 N., R.1 E.
 Fnd. Rec. Conc. Mon.
 Fnd. Old Blaze - S.40°E - 2.65' - 24" Dead Oak
 Fnd. Tag #14200 - S.55°W - 27.51' - 24" Maple
 Fnd. Tag #14200 - N.50°E - 13.61' - 36" Pine
 Fnd. Spk - S.65°W - 7.82' - 15" Maple
 NO ORIGINAL CORNER EVIDENCE FOUND

A-2 West 1/4 Cor. Sec. 6, T.30 N., R.1 E.
 Fnd. Rec. 1/2" Irons
 Fnd. Iron #18660 - East - 54.85'
 Fnd. 1/2" Iron @ A-3 - South 2698.01'
 Fnd. Conc. Mon. @ A-1 - North 2213.02'
 NO ORIGINAL CORNER EVIDENCE FOUND

This Cor. is the STANDARD CORNER, on the MICHIGAN MERIDIAN at the THIRD CORRECTION LINE.

This Cor. is the STANDARD CORNER, on the MICHIGAN MERIDIAN.

Approved by Montmorency County Peer Review on Sept. 24, 1993, as the best available evidence of the position of the original corner.

Approved by Montmorency County Peer Review on Sept. 24, 1993, as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-1 Northwest Cor., Sec. 6, T.30 N., R.1 E.
 Set Mont. Co. Re-Mon. Cap on Endc. Cncl. Mon.
 Corner is in Sngl Strand E-W Fnc Line
 Corner is ±536' W. of C.L. of Meridian Line Rd.
 N.50°E. - 13.61' - Set Tag SE Sd. 36" Pine (Old Wit)
 S.65°E. - 13.39' - Set Tag N. Sd. 20" Maple
 S.40°E. - 2.65' - Old Blaze in 24" Dead Oak
 S.55°W. - 27.51' - Set Tag SE Sd. 24" Maple (Old Wit)
 S.65°W. - 7.82' - Set tag N. Sd. 15" Maple (Old Wit)
 Set Treated R.T. Post Along Side Corner

A-2 West 1/4 Cor. Sec. 6, T.30 N., R.1 E.
 Set Mont. Co. Re-Mon. Cap on Fnd. 1/2" Iron.
 Corner is ±4' W. of W. Edge of B.T. Rd.
 Corner is in line with Fence to East
 N.70°E. - 88.28' - Set Tag S. Sd. 10" Twin Maple
 S.88°E. - 54.85' - Iron & Tag #18660
 N.80°W. - 24.05' - Set Tag S. Sd. 8" Oak
 N.40°W. - 45.61' - Set Tag SW Sd. 60" Maple
 SOUTH -- 574.68' (R-573.76') Fnd 1/2" Iron in line
 with Fnc to W. @ Cor. M-2 T30N-R1W
 Set Treated R.T. Post on E. Sd. Rd., Opp. Cor.

NOTE: All witnesses Marked with DBL. Headed Nails & I.D. Tag #25852

Signed by Frederick J. King
Surveyor's Michigan License No. 25852

Date Dec 23, 1993

